

3/27/03
3:30
3/28/03
NOD

PUB. SEWER STATUS VERIFIED BY _____

ISSUE DATE:

3/19/03

APPROVAL DATE:

3/28/03

PERMIT
INDEXED

P 518563

A REPAIR

ON-SITE SEWAGE DISPOSAL SYSTEM
HOWARD COUNTY HEALTH DEPARTMENT
BUREAU OF ENVIRONMENTAL HEALTH

02-241072

Feaga and Son Excavating

IS PERMITTED TO

INSTALL ☐

ALTER ☒

ADDRESS: 1625 Henryton Road

PHONE NUMBER: 410-442-5623

SUBDIVISION: Rolling Ridge

LOT NUMBER: 1

ADDRESS: 8447 Rolling Ridge Court

PROPERTY OWNER: Quesenberry

SEPTIC TANK CAPACITY (GALLONS):

EX.

PUMP CHAMBER CAPACITY (GALLONS):

—

NUMBER OF BEDROOMS:

3

SQUARE FEET PER BEDROOM:

180

LINEAR FEET OF TRENCH REQUIRED:

120' + 60'

TRENCHES:	Trench to be 2.0 feet wide. Inlet 5.0 feet below original grade. Bottom maximum depth 9.5 feet below original grade. Effective area begins at 6.0 feet below original grade. 4.5 feet of stone below distribution pipe.
LOCATION:	Cut existing trench and install distribution box at location 100' from neighbor's existing well. Install two 60-65" trenches at least 10' uphill of existing drywell.
PURPOSE:	In support of plat approval to revise BRLs to accommodate new garage. PUMP PIT INSTALLED WHEN D/W FAILS

PLANS APPROVED: MER

DATE: 3/19/03

NOTE: PERMIT VOID AFTER 2 YEARS

NOTE: CONTRACTOR RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS

NOTE: WATERTIGHT SEPTIC TANKS REQUIRED

NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE 100 FEET FROM ANY WATER WELL

NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS

**NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS
RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM
PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT
CALL 410-313-2640 FOR INSPECTION OF SEPTIC SYSTEM**

P 518563
P 518563

NOT TO SCALE

A hand-drawn site plan on a grid background. The plan shows a property bounded by 'OLD FRED. RD' on the left and 'ROLLING RIDGE CT' at the bottom. A horizontal line at the top is labeled 'PROP. LINE'. Inside the property, there is an 'EX. WELL' (a small circle), an 'EX. A.G. POOL' (an oval), an 'EX. HOUSE' (a rectangle), and a large, irregular shape representing a driveway or yard. To the right of the house, there is a 'DISCONNECTED TRENCH' (a rectangle) and a 'D/W C/O' (a circle). A 'PROP. LINE' is also indicated on the right side, with a note 'DO NOT PORT 6' OFF PROP LINE'. Various measurements and labels are scattered throughout, including '18', '9', '31', '32', '100', '8', '7', 'EX. S.T. C/O', and 'EX. SHE'.

PROP. LINE

EX. WELL

EX. A.G. POOL

EX. HOUSE

EX. S.T. C/O

DISCONNECTED TRENCH

D/W C/O

DO NOT PORT 6' OFF PROP LINE

EX. SHE

18

9

31

32

100

8

7

OLD FRED. RD

ROLLING RIDGE CT

ROAD

SEPTIC TANK DATA

ADJ. SEPTIC TANK 1 LEVEL EX.

WELL CAPACITY 1000 GAL

SEAM LOC _____

TANK LID DEPTH _____

BAFFLES _____

BAFFLE FILTER _____

MANHOLE LOC _____

6" PORT LOC _____

WATERTIGHT TEST _____

SEPTIC TANK 2 LEVEL _____

CAPACITY _____ GAL

SEAM LOC _____

TANK LID DEPTH _____

BAFFLES _____

BAFFLE FILTER _____

MANHOLE LOC _____

6" PORT LOC _____

WATERTIGHT TEST _____

PRE-CONSTRUCTION 3/27/03 PIPE IN EX. TRENCH AT 6' - TOO DEEP TO USE AS PLANNED; TRENCHES TO BE INSTALLED BUT NOT CONNECTED; AT TIME OF D/W INSTALLATION FAILURE, D/W TO BE ABANDONED, PUMP PIT INSTALLED FOR PUMPING TO NEW TRENCHES (MR)

3/28/03 TRENCHES INSTALLED W/O CONNECTION AS DISCUSSED; EX. TRENCH DISCONNECTED COMPLETELY FROM EX. D/W; D/W INTACT, TO BE ABANDONED IN FAVOR OF PUMPED SEPTIC SYSTEM WHEN D/W FAILS; BLDR ADVISED D/W LIFE IS LIKELY LIMITED; H₂O IN D/W ~2' BELOW LID (MR)

FINAL INSPECTOR M. Ripkin DATE OF APPROVAL 3/28/03