

# PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

P 37208

A 32184

HOWARD COUNTY  
BUREAU OF ENVIRONMENTAL HEALTH

~~882-2330~~  
461-9933

INDEXED

05-393590

ELICOTT CITY

DISTRICT

DATE

Gene Ebel

IS PERMITTED TO INSTALL ☒ ALTER ☐

ADDRESS 1509 Defense Highway, Gambrills, MD 21054 PHONE 261-6300

SUBDIVISION Jocelyn Acres III ROAD 13411 Rich Lynn Ct. LOT 10 Sec III

PROPERTY OWNER Yulando Vriago Tim Ebel

ADDRESS 9190 Levell Drive  
Chevy Chase, Maryland 20815

IF GARBAGE GRINDER IS USED INCREASE SEPTIC TANK CAPACITY BY 50% AND ABSORPTION AREA BY 22%.

GARBAGE GRINDER? YES ☐ NO ☒

SEPTIC TANK CAPACITY 1000 GALLONS NUMBER OF BEDROOMS 3

BLDG. PERMIT SIGNED

AND RETURNED

Serial # 57747

2-story Addition

TRENCHES - 220 sq. ft. per bedroom. Trench to be 2 feet wide. Inlet 3 feet below original grade. Bottom maximum depth 8 feet below original grade. Effective area begins at 3 feet below original grade. 5 feet of stone below distribution pipe.

LOCATION - Start the first trench 260 feet from the front lot line and 70 feet from the left lot line as seen when facing the property from Rich Lynn Court. Run trench(s) along contour toward left-rear corner of property.

NOTE - No Trench to exceed 100 feet in length. If more than one trench used, a distribution box is required. Call for inspection of trench(s) before and after gravel is installed. Provide 6" - 8" diameter cleanout and cap to grade or above on septic tank.

BUILDING PERMIT SIGNED

AND RETURNED

11/23/04 - 800151338 - POOL HOUSE

11/30/04 - 800151336 - REMODEL EXISTING BDRM

PLANS APPROVED BY C. Williams

DATE 6/19/86

COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

NOTE: IF TRENCH IS USED CALL FOR INSPECTION BEFORE AND AFTER PLACING GRAVEL IN TRENCH.

NOTE: NO DRY WELL SHALL EXCEED 15 FOOT IN DIAMETER. NO ABSORPTION TRENCH TO EXCEED 100 FEET IN LENGTH.

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON OR SCHEDULE 40 PVC OR ABS.

PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL. STAND PIPES MUST BE 6 INCHES IN DIAMETER. CAST IRON, CONCRETE OR TERRA COTTA, OR PVC OR ABS ACCEPTED. IF TOP OF SEPTIC TANK IS DEEPER THAN 3 FEET MANHOLE TO GRADE REQUIRED.

BLDG. PERMIT SIGNED

AND RETURNED

Serial # 44964

Strip Shed

\*INSTALLER IS RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT

CALL 882-2330 FOR INSPECTION OF SEPTIC SYSTEMS.

EH - 2-1082

A  
32184



