

PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

INDEXED

ELLICOTT CITY

DISTRICT 5th

DATE 6/18/73

Jack Fyock

IS PERMITTED TO INSTALL ☒ ALTER

ADDRESS Ten Oaks Road, Glenelg, Maryland

PHONE 286-2939

A SEWAGE DISPOSAL SYSTEM LOCATED AT

SUBDIVISION ROAD Reservoir Road

LOT Parcel A & A-1

PROPERTY OWNER Otis Mauck (Lawrence E. Altman, Jr.)

Phone: Ju 9-2957

ADDRESS Fulton, Md.

SPECIFICATIONS

4 bedrooms

DRAIN FIELD DEPTH FEET. BOTTOM AREA SQ. FT.

SEEPAGE PITS ADSORBENT SIDE-WALL AREA SQ. FT.

SEPTIC TANK CAPACITY 1250 GALLONS

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 22% & TANK CAPACITY 30%.

OTHER DRY WELL - Total absorbent sidewall area to be 600 ft. for 4 bedrooms (150 sq. ft. per bedroom). Effective absorbent sidewall area to start at 2 1/2 ft. below original grade and maximum depth 12 ft. Inlet can come in at 4 ft. below original grade. Location 350 ft. down left side line and 200 ft. in from left side. as seen when facing lot from Reservoir Road. 14 ft. x 50 ft.

NOTE: ALL PIPE FROM HOUSE TO DRY WELL MUST BE CAST IRON.

PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STEEL PIPE ON SEPTIC TANK AND DRY WELL.

PLANS APPROVED BY

Charles B. Stricker & P. F. Frowalt

DATE 4/3/73

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

A 17138