



Sam's Excavating, Inc.

P.O. Box 0157
Fulton, MD 20759-0157
Cell Phone: (443) 277-7915

October 5, 2020

Theoni Hiotis
6612 Seneca Farm Rd
Columbia MD 21046

410 922 9526

RE: Sewer line from county connection to property line

The following is our proposal for the excavating and installation of a sewer line to property line, core drill and install manhole drop.

Includes:

1. Backhoe and operator
2. Truck
3. Installation of 4 inch Schedule 35 PVC from manhole to property line
4. 40 feet of 4 inch schedule 35 PVC
5. 1 Sewer block 4 inch
6. Gravel 57 stone and CR6 for under road
7. Asphalt patch cold patch
8. Steel plates milling for plates
9. Shoring boxes
10. Traffic control
11. Labor plumber
12. Backfill to rough grade
13. Seed and straw

Excludes:

1. If Backhoe hits any rock or water that we can't dig, there will be an extra charge. (Price for this to be determined at time of occurrence.)


Total Contract amount \$10,500.00

Payments: Deposit of \$5,250.00 before we start job. \$5,250.00 at completion of job

If you have any questions please call me at 443-277-7915.

Sincerely,

Sam Wilkerson, President
Sam's Excavating, Inc.


Signature Date
7-6-21