



# Howard County Health Department

Maura J. Rossman, M.D., Health Officer

## Bureau of Environmental Health

8930 Stanford Boulevard, Columbia, MD 21045

Main: 410-313-2640 | Fax: 410-313-2648

TDD 410-313-2323 | Toll Free 1-866-313-6300

[www.hchealth.org](http://www.hchealth.org)

Facebook: [www.facebook.com/hocohealth](https://www.facebook.com/hocohealth)

RECEIPT DATE: 12/9/21

### ONSITE SEWAGE DISPOSAL SYSTEM

P 570875

APPROVAL DATE: \_\_\_\_\_

### PERMIT:

**Upgrade**

A \_\_\_\_\_

PROPERTY ADDRESS: 2605 Roxbury Mills Road (Route 97)

SUBDIVISION: Green Meadows

LOT: 1

TAX ID: \_\_\_\_\_

CONTRACTOR: Fogles Septic Clean Inc.

EMAIL: kim@foglesinc.com

CONTRACTOR ADDRESS: 580 Obrecht Road, Sykesville, MD 21784

PHONE: 410-795-5670

PROPERTY OWNER: Kevin and Dolores Garvey

EMAIL: \_\_\_\_\_

OWNER ADDRESS: 2605 Roxbury Mills Road, Glenwood, MD 21738

PHONE: \_\_\_\_\_

SEPTIC TANK SIZE (GALLONS): 1500 TB PUMP CHAMBER CAPACITY (GALLONS): 1500 TB PUMP SIZE: WEDS 11H

NUMBER OF BEDROOMS: 4 HOUSE SQ. FT. \_\_\_\_\_ APPLICATION RATE: 0.8

DISTRIBUTION SYSTEM: GRAVITY FED ☒ LOW PRESSURE DOSED ☐

TRENCHES:	LINEAR FEET REQUIRED: <u>150'</u>	INLET DEPTH: <u>2'</u>
	TRENCH WIDTH: <u>2'</u>	MAXIMUM BOTTOM DEPTH: <u>7.5'</u>
	MINIMUM SPACE BETWEEN TRENCHES: <u>10'</u>	EFFECTIVE AREA BEGINNING DEPTH: _____
LOCATION:	TO BE STAKED BY SANITARIAN DURING PRE-CONSTRUCTION INSPECTION.	
NOTES:	<u>INSTALL 3x 50' TRS</u>	

ISSUED BY: CABAHUB 001997 ISSUE DATE: 01/18/2022 EXPIRATION DATE: 01/18/2023

**NOTE: CONTRACTOR MUST SCHEDULE A PRE-CONSTRUCTION INSPECTION PRIOR TO BEGINNING ANY INSTALLATION**

**NOTE: CONTRACTOR MUST SCHEDULE AN INSPECTION AND GAIN APPROVAL OF ALL COMPONENTS PRIOR TO COVERING**

**NOTE: STONE MUST BE APPROVED BY HEALTH DEPARTMENT AND GRAVEL TICKET MUST BE AVAILABLE FOR REVIEW.**

**NOTE: WATERTIGHT SEPTIC TANKS REQUIRED**

**NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE AT LEAST 100 FEET DOWNGRADIENT FROM ANY WATER WELL**

**NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS**

**NOTE: AN ELECTRICAL PERMIT IS REQUIRED FOR INSTALLATION OF ANY ELECTRICAL COMPONENTS OF THE SYSTEM**

☐ ELECTRICAL PERMIT ISSUED E \_\_\_\_\_


**NOTE: THE HCHD DOES NOT WARRANTY ANY SYSTEM AND CANNOT GUARANTEE THE PERFORMANCE OF THIS SYSTEM AS DESIGNED. BY ACCEPTING THIS PERMIT, THE OWNER AND/OR APPLICANT ACKNOWLEDGE THAT THE SPECIFICATIONS DETAILED IN THIS DESIGN ARE ONE POSSIBLE OPTION AND THAT THE HCHD WILL REVIEW OTHER PROPOSALS. YOU HAVE THE OPTION TO SEEK THE ADVICE OF A QUALIFIED DESIGN CONSULTANT OR PROFESSIONAL ENGINEER FOR FURTHER GUIDANCE.**

**NOTE: MDE RECOMMENDS SEPTIC TANKS, BAT, AND OTHER PRETREATMENT UNITS BE PUMPED AT A FREQUENCY ADEQUATE TO ENSURE THAT SOLIDS ARE NOT DISCHARGED TO THE DISPOSAL AREA**

**NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.**

**PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT.**

**CALL 410-313-1771 TO SCHEDULE INSPECTIONS.**



TRENCH/DRAINFIELD DATA		
WIDTH	INLET	BOTTOM
2'	2'	7.5'
NUMBER OF TRENCHES	3	
TOTAL LENGTH	150 F	
ABSORPTION AREA	450 SF +	
DISTRIBUTION BOX LEVEL	PUMP	
DISTRIBUTION BOX BAFFLE	90 TURN	
DISTRIBUTION BOX PORT	YES	

+ D Box RISER

SEPTIC TANK DATA	
SEPTIC TANK 1 LEVEL	YES
MANUFACTURER	BABCOCK
CAPACITY	1500 GAL
SEAM LOC	TOP
TANK LID DEPTH	3.5' - 3'
BAFFLES	YES
BAFFLE FILTER	-
MANHOLE LOC	FRONT/BACK
6" PORT LOC	-
WATERTIGHT TEST	-
SLOTTED	YES
DATE ON LID	12/16/2021
PUMP/SEPTIC TANK LEVEL	YES
MANUFACTURER	BABCOCK
CAPACITY	1500 GAL
SEAM LOC	TOP
TANK LID DEPTH	3.5' - 3'
BAFFLES	-
BAFFLE FILTER	-
MANHOLE LOC	-
6" PORT LOC	-
WATERTIGHT TEST	-
SLOTTED	TB
DATE ON LID	12/16/2021

PRE-CONSTRUCTION:

01/18/2022 LAID OUT 3x50' TRS ON contour 12' c/c. Confirmed  
SYSTEM SPEC 7.5' TO BOTTOM 2' INLET 6' STONE

INSTALLATION:

01/19/2022 TRENCHES COMPLETE; D BOX SET COR OF LID  
KNICKED OFF TO FIT RISER; 35' FM INSTALLED  
1/24/22 FM installed. 01/24/2022 SL TIED IN TO EX LINE, TANKS  
SET, FORCE MAIN COMPLETE. 2/16/22 - p: A ok, floats look good, pump working  
and water flow observed @ dbox, Alarm operational; circuit boxes for p: & are on the  
outside of the house - ok to continue w/ backfilling

FINAL INSPECTOR

R. Rappaport

DATE OF APPROVAL

2/16/22

FORCE MAIN  
KIRTEC PVC  
2" SCH 40 280PSI @ 73°F  
ASTM D 1785

\* SYSTEM ON PROPERTY  
DESPITE APPEARANCE  
ON ASBUILT  
HERE

PROP LINE  
88'

EX TR

100' WELL ARE

60'

Pool

123'

61'

168'

102'

10.5'

18'

30'


DRIVE  
36'



House

158'

SDA

NOT TO SCALE





VICINITY MAP ADC MAP: 9C3 SCALE: 1"=2000'

BENCHMARKS (HORIZONTAL: NAD83, VERTICAL: NAVD83)			
STA.	NORTHING	EASTING	ELEVATION
14FC	595630.340	1306560.213	619.264
14CB	598079.749	1306428.279	590.999


LEGEND

---	BOUNDARY LINE
---	LOT LINE
---	EASEMENT
---	EXISTING CONTOUR MAJOR
---	EXISTING CONTOUR MINOR
---	EXISTING TREE LINE
---	SOIL LINE
---	EXISTING FENCE
---	EXISTING WELL
---	PROPOSED ALTERNATE WELL LOCATION

- GENERAL NOTES
- Any change to the locations of depths to any components must be approved by an engineer and the Howard County Health Department prior to installation. A revised site plan may be required.
  - The cover over the proposed septic tank will be 2.35 ft and pump chamber will be 2.69 ft. Both tanks are rated as traffic bearing tanks. See attached drawings for additional detail. These depths of cover are predicated on 1% fall on the sewer line from the inlet side of the existing septic tank (to be abandoned) to the location of the proposed septic tank.
  - Electrical work for the installation must be performed by a licensed electrician.
  - The well (Tag # HO 73-2777) has been field located and is accurately shown.
  - All wells and septic systems located within 100 ft. of the property boundaries and 200 ft. down gradient of any wells and/or septic systems have been shown.

Approved Septic System Plan  
Howard County Health Department  
1500-gal septic tank with  
1500-gal pump tank and Gould's WG5511 H pump  
Gravity Distribution for 4-bedroom SFD  
Signature: [Signature] Date: 1/24/2020

LAYOUT PLAN



OWNER/DEVELOPER  
KEVIN & MARIA GARVEY  
2605 ROUTE 97  
GLENWOOD, MD 21738  
443-506-5112





NO.	REVISION	DATE

REPAIR OF SEWAGE DISPOSAL PLAN  
2605 ROUTE 97  
GREEN MEADOWS SUBDIVISION - LOT 8  
ZONE: RR-DEO

TAX MAP: 14, GRID: 11 ELECTION DISTRICT: 4	PARCEL: 217 HOWARD COUNTY, MARYLAND
SEWAGE DISPOSAL SYSTEM DESIGN PREPARED BY JAMES R. POWELL 421 ROCKWAY ROAD CATONSVILLE, MARYLAND 21228 443-900-3169	PROJECT NO.: 4177 DESIGNED BY: JRP DRAWN BY: KTG CHECKED BY: JRP DATE: JAN. 2, 2020

SHEET: 1 OF 2


Signature: [Signature] DATE: 1-8-20



- CONTROL PANEL INFORMATION AND DOSE CALCULATIONS**
- Control panel will be an SJE Rhombus Installer Friendly Series (IFS), simplex pump, single phase, 115-volt, demand dose. The panel will include an event counter and an elapsed time meter for the pump run. Float system must include: Pump Off, Pump On and High-Water Alarm.
  - The high-water alarm must be on a separate electrical circuit.
  - The effluent will be pumped to a distribution box, equipped with a surge baffle. The effluent will then proceed via gravity flow to the three separate deep trench systems comprising the initial installation area. The trenches will be demand dosed.
  - Install quick disconnect for the pump (Goulds series 3885, WE 05HH, 1/2 Hp, 1 phase, 115 volts)
  - Dose Calculations - peak daily design flow is 600 gpd (based on four bedrooms x 150 gal./bedroom/day)
    - Total length of force main (2" fusible HDPE pipe) is 313'
    - Volume of force main - 313' x 17.4 gal./100 ft. = 54.5 gal.
    - Average flow estimated to be 60% of peak flow - therefore 600 gpd x 0.6 = 360 gpd. It is desirable to have the pump operate a minimum of 3 times/24-hour period. Consequently, the minimum dose to be delivered to the deep trench systems is 360 gpd avg flow ÷ 3 = 120 gal. delivered to trench system
    - 120 gal. + 54.5 gal. storage in force main = 174.5 gal.
  - The pump chamber is manufactured by Mayer Bros., Inc.
    - Storage calculations - inside dimensions of tank - 4.58' x 12.92' (excluding 4" width for center wall) x 7.48 gal./cu. Ft. = 442.6 gal./ft. of sewage in tank
    - 442.6 gal./ft. of sewage in tank ÷ 12" = 36.88 gal./inch storage
    - 174.5 gal ÷ 36.88 gal./inch = 4.7" - use 5" between pump on and off float
    - 5" between pump on and pump off float x 36.88 gal./inch = dose flow of 184.4 gal.
  - Storage capacity above the high-water alarm float
    - There is 17" of storage in the pump chamber between the high-water alarm float and the invert of the inlet pipe. Using the calculation above there is 36.88 gal./inch of storage in the tank - providing 627 gal. storage.

- SEWAGE DISPOSAL SYSTEM DESIGN CALCULATIONS FOR ONE INITIAL AND TWO FUTURE REPLACEMENT SYSTEMS**
- INITIAL SYSTEM INSTALLATION** - for an existing four-bedroom dwelling
    - Design on Soil Percolation Test 2A - soil loading rate 0.8 gal./sq. ft./day
    - Effective area beginning depth - 4'
    - Total trench depth 7.5'
    - 4 bedrooms x 150 gal./day/bedroom = 600 gpd peak design flow
    - 600 gpd ÷ 0.8 gal./sq. ft./day soil loading rate = 750 sq. ft. effective area
    - 750 sq. ft. effective area ÷ 2 ft. shallow trench width = 375 ft. shallow trench
    - 375 ft. shallow trench x deep trench conversion factor (2 + 2/2 + 1 + 2 (3.5) or 0.4) = 150 ft. of 7.5' deep
    - Elect to use three 50' long trenches, 2 ft. wide, 7.5' deep - separation distance is 10 ft. measured edge to edge or 12' on center (shown as Trenches 1, 2, 3 on site plan)
  - FIRST REPLACEMENT SYSTEM** - for an existing four-bedroom dwelling
    - Design on Soil Percolation Test 9A - soil loading rate 0.8 gal./sq. ft./day
    - Effective area beginning depth 4'
    - Total trench depth 7'
    - 4 bedrooms x 150 gal./day/bedroom = 600 gpd peak design flow
    - 600 gpd ÷ 0.8 gal./sq. ft./day soil loading rate = 750 sq. ft. effective area
    - 750 sq. ft. effective area ÷ 2 ft. shallow trench width = 375 ft. shallow trench
    - 375 ft. shallow trench x deep trench conversion factor (2 + 2/2 + 1 + 2 (3) or 0.44) = 165 ft. of 7' deep
    - Elect to use three 55' long trenches, 2 ft. wide, 7' deep - separation distance is 10 ft. measured edge to edge or 12' on center (shown as Trenches 4, 5, 6 on site plan)
  - SECOND REPLACEMENT SYSTEM** - for an existing four-bedroom dwelling
    - Design on Soil Percolation Tests 10A, 11 - soil loading rate 0.6 gal./sq. ft./day
    - Effective area beginning depth 3.5'
    - Total trench depth 6'
    - 4 bedrooms x 150 gal./day/bedroom = 600 gpd peak design flow
    - 600 gpd ÷ 0.6 gal./sq. ft./day soil loading rate = 1,000 sq. ft. effective area
    - 1,000 sq. ft. effective area ÷ 2 ft. shallow trench width = 500 ft. shallow trench
    - 500 ft. shallow trench x deep trench conversion factor (2 + 2/2 + 1 + 2 (2.5) or 0.5) = 250 ft. of 6' deep
    - Elect to use three 63' long trenches (shown as Trenches 7, 8, 9 on site plan); and one trench being split into two 32' lengths of run (shown as Trenches # 10A and #10B on the site plan). The trenches for 10A and 10B will be connected via end feed on each end of the 32 ft. long runs as shown on the site plan. The trenches will be 2 ft. wide, 6' deep - separation distance is 10 ft. measured edge to edge or 12' on center

- CONSTRUCTION DETAIL**
- The existing dwelling consists of four bedrooms.
  - The existing sewage disposal system currently serving the dwelling will be abandoned; with the septic tank being pumped by a licensed septic waste hauler, crushed and filled with clean soil.
  - The proposed replacement system will consist of a 1,500-gallon two compartment septic tank, 1,500-gallon pump chamber and three deep absorption trenches. The trenches will be demand dosed.
  - The septic tank will be traffic bearing as the cover on the tank will be 3.56' and will be manufactured by Mayer Brothers, Inc. The 1,500-gallon pump chamber will have 3.89' of cover and will also be traffic bearing. The pump chamber will be manufactured by Mayer Brothers, Inc. and will have a center wall on the interior of the tank for structural support. There will be a 12" x 12" opening at the bottom of the center wall to allow for flow equalization during pump operation. **NOTE: THE PUMP CHAMBER IS NOT NORMALLY A STOCKED ITEM. PLEASE ALLOW FOUR (4) WEEKS BETWEEN ORDERING THE TANK AND DELIVERY.**
  - The deep absorption trench design will consist of three trenches; each trench to be 50 ft. long, 2 ft. wide and 7.5 ft. deep. The perforated pipe will be installed 18" below grade with 6 ft. of Md. #2 stone below the trenches and the separation distance between the trenches will be 10 ft., measured edge to edge (12 ft. on center). Two inches of stone will be placed over the lateral piping, with geotextile fabric (spun, not woven) on top and the remaining 16" being soil backfill to the ground surface.
  - The force main from the pump chamber to the distribution box shall be 2" fusible HDPE pipe.
  - A distribution box will be installed and shall have a surge baffle installed directly opposite the force main influent line. The distribution box shall be equipped with a concrete manhole riser to grade with a concrete lid.
  - Observation pipes shall be installed at the end of each trench. The observation pipes shall be 4" Sch. 40 pvc pipes and shall have 1/2" perforations drilled on one side at 6" intervals from the bottom of the stone trench to the top of the lateral distribution pipe. The remainder of the observation pipe from that point to the cap (top) will be solid Sch. 40 pvc pipe. The observation pipe caps will be placed below grade in a plastic turf box, with the lids at final grade. The plastic turf box will be Rain Bird round boxes, 10" in diameter, 10" high, Model PVB 10 RND and be supported by bricks at the bottom.
  - A Goulds submersible effluent pump Model 3885, series WE0511HH, 1/2 Hp, single phase, 115 volts will be installed in the pump chamber.
  - A "float tree" shall be placed in the pump chamber with the floats attached to it as shown. The float tree shall be 4" Sch. 40 pvc pipe.
  - The high-water alarm will be wired to separate circuit breaker from that of the pump.




SEWAGE DISPOSAL SYSTEM DESIGN PREPARED BY:  
JAMES POWELL  
421 ROCKWAY ROAD  
CATONVILLE, MARYLAND 21228  
443-993189

SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_

OWNER/DEVELOPER  
KEVIN & MARIA GARVEY  
2605 ROUTE 97  
GLENWOOD, MD 21738  
443-506-5112

MONARCH PRODUCTS COMPANY, INC.  
YORK HAVEN, PA.

NOTES:  
1. H-20 TRAFFIC RATED FOR 1' TO 5' OF EARTH COVER.  
2. CONCRETE TO BE 5000 PSI MIN. @ 28 DAYS.  
3. REINFORCING STEEL TO BE PER ASTM A615, GRADE 60.  
4. BOX WT. (W/BAFFLES)=19,400#, LID WT.=5,800#.



1500 GALLON 1 COMPARTMENT TRAFFIC  
RATED PUMP TANK

PT-1500-1TR

CONTROL PANEL INFORMATION

AND DOSE CALCULATIONS

- Control panel will be an SJE Rhombus Installer Friendly Series (IFS), simplex pump, single phase, 115-volt, demand dose. The panel will include an event counter and an elapsed time meter for the pump run. Float system must include: Pump Off, Pump On and High-Water Alarm.
- The high-water alarm must be on a separate electrical circuit.
- The effluent will be pumped to a distribution box, equipped with a surge baffle. The effluent will then proceed via gravity flow to the three separate deep trench systems comprising the initial installation area. The trenches will be demand dosed.
- Install quick disconnect for the pump (Goulds series 3885, WE 05H, 1/2 Hp, 1 phase, 115 volts)
- Dose Calculations – peak daily design flow is 600 gpd (based on four bedrooms x 150 gal./bedroom/day)
  - Total length of force main (2" fusible HDPE pipe) is 388'
  - Volume of force main – 388' x 17.4 gal./100 ft. = 67.5 gal.
  - Average flow estimated to be 60% of peak flow – therefore 600 gpd x 0.6 = 360 gpd. It is desirable to have the pump operate a minimum of 3 times/24-hour period. Consequently, the minimum dose to be delivered to the deep trench systems is 360 gpd avg flow ÷ 3 = 120 gal. delivered to trench system
  - 120 gal. + 67.5 gal. storage in force main = 187.5 gal.
- The pump chamber is manufactured by Monarch Products Co., Inc.
  - Storage calculations – inside dimensions of tank – 4' x 10.67' x 7.48 gal./cu. Ft. = 319.2 gal./ft. of sewage in tank
  - 319.2 gal./ft. of sewage in tank ÷ 12" = 26.6 gal./inch storage
  - 187.5 gal ÷ 26.6 gal./inch = 7" – use 7" between pump on and off float
- Storage capacity above the high-water alarm float
  - There is 29" of storage in the pump chamber between the high-water alarm float and the invert of the inlet pipe. Using the calculation above there is 26.6 gal./inch of storage in the tank – providing 771 gal. storage.

SEWAGE DISPOSAL SYSTEM DESIGN CALCULATIONS


FOR ONE INITIAL AND TWO  
FUTURE REPLACEMENT SYSTEMS

- INITIAL SYSTEM INSTALLATION – for an existing four-bedroom dwelling
  - Design on Soil Percolation Test 2A – soil loading rate 0.8 gal./sq. ft./day
  - Effective area beginning depth – 4'
  - Total trench depth 7.5'
  - 4 bedrooms x 150 gal./day/bedroom = 600 gpd peak design flow
  - 600 gpd ÷ 0.8 gal./sq. ft./day soil loading rate = 750 sq. ft. effective area
  - 750 sq. ft. effective area ÷ 2 ft. shallow trench width = 375 ft. shallow trench
  - 375 ft. shallow trench x deep trench conversion factor (2 + 2/2 + 1 + 2 (3.5) or 0.4) = 165 ft. of 7.5' deep
  - Elect to use three 50' long trenches, 2 ft. wide, 7.5' deep – separation distance is 10 ft. measured edge to edge or 12' on center (shown as Trenches 1, 2, 3 on site plan)
- FIRST REPLACEMENT SYSTEM – for an existing four-bedroom dwelling
  - Design on Soil Percolation Test 9A – soil loading rate 0.8 gal./sq. ft./day
  - Effective area beginning depth 4'
  - Total trench depth 7'
  - 4 bedrooms x 150 gal./day/bedroom = 600 gpd peak design flow
  - 600 gpd ÷ 0.8 gal./sq. ft./day soil loading rate = 750 sq. ft. effective area
  - 750 sq. ft. effective area ÷ 2 ft. shallow trench width = 375 ft. shallow trench
  - 375 ft. shallow trench x deep trench conversion factor (2 + 2/2 + 1 + 2 (3) or 0.4) = 165 ft. of 7' deep
  - Elect to use three 55' long trenches, 2 ft. wide, 7' deep – separation distance is 10 ft. measured edge to edge or 12' on center (shown as Trenches 4, 5, 6 on site plan)
- SECOND REPLACEMENT SYSTEM – for an existing four-bedroom dwelling
  - Design on Soil Percolation Tests 10A, 11 – soil loading rate 0.6 gal./sq. ft./day
  - Effective area beginning depth 3.5'
  - Total trench depth 6'
  - 4 bedrooms x 150 gal./day/bedroom = 600 gpd peak design flow
  - 600 gpd ÷ 0.6 gal./sq. ft./day soil loading rate = 1,000 sq. ft. effective area
  - 1,000 sq. ft. effective area ÷ 2 ft. shallow trench width = 500 ft. shallow trench
  - 500 ft. shallow trench x deep trench conversion factor (2 + 2/2 + 1 + 2 (2.5) or 0.5) = 250 ft. of 6' deep
  - Elect to use three 63' long trenches (shown as Trenches 7, 8, 9 on site plan); and one trench being split into two 32' lengths of run (shown as Trenches # 10A and #10B on the site plan). The trenches for 10A and 10B will be connected via end feed on each end of the 32 ft. long runs as shown on the site plan. The trenches will be 2 ft. wide, 6' deep – separation distance is 10 ft. measured edge to edge or 12' on center.
  - This trench layout will require the system incorporate low-pressure dosing design.

CONSTRUCTION DETAIL


- The existing dwelling consists of four bedrooms.
- The existing sewage disposal system currently serving the dwelling will be abandoned; with the septic tank being pumped by a licensed septic waste hauler, crushed and filled with clean soil.
- The proposed replacement system will consist of a 1,500-gallon two compartment septic tank, 1,500-gallon pump chamber and three deep absorption trenches. The trenches will be demand dosed.
- The septic tank will be traffic bearing and will be manufactured by Mayer Brothers, Inc. The septic tank will have 2.35' of cover, which is based on the sewer line between the inlet side of the existing septic tank (TBA) and the proposed septic tank being installed with 1% fall. The 1,500-gallon pump chamber will have 2.69' of cover and will also be traffic bearing. The pump chamber will be manufactured by Monarch Products Company, Inc. NOTE: THE PUMP CHAMBER IS NOT NORMALLY A STOCKED ITEM. PLEASE ALLOW SEVERAL WEEKS BETWEEN ORDERING THE TANK AND DELIVERY.
- The deep absorption trench design will consist of three trenches; each trench to be 50 ft. long, 2 ft. wide and 7.5 ft. deep. The perforated pipe will be installed 24" below grade with 5.5 ft. of Md. #2 stone below the lateral pipe and the separation distance between the trenches will be 10 ft., measured edge to edge (12 ft. on center).
- The force main from the pump chamber to the distribution box shall be 2" fusible HDPE pipe.
- A distribution box will be installed and shall have a surge baffle installed directly opposite the force main influent line. The distribution box shall be equipped with a concrete manhole riser to grade with a concrete lid.
- Observation pipes shall be installed at the end of each trench. The observation pipes shall be 4" Sch. 40 pvc pipes and shall have 1/2" perforations drilled on one side at 6" intervals from the bottom of the stone trench to the bottom of the lateral distribution pipe. The remainder of the observation pipe from that point to the cap (top) will be solid Sch. 40 pvc pipe. The observation pipe caps will be placed below grade in a plastic turf box, with the lids at final grade. The plastic turf box will be Rain Bird round boxes, 10" in diameter, 10" high, Model PVB 10 RND and be supported by bricks at the bottom.
- A Goulds submersible effluent pump Model 3885, series WE0511H, 1/2 Hp, single phase, 115 volts will be installed in the pump chamber.
- A "float tree" shall be placed in the pump chamber with the floats attached to it as shown. The float tree shall be 4" Sch. 40 pvc pipe.
- The high-water alarm will be wired to separate circuit breaker from that of the pump.

DEEP TRENCH PROFILE  
AND  
OBSERVATION PIPE DETAIL




PLAN NOT TO SCALE

HYDRAULIC PROFILE



HORIZONTAL SCALE 1" = 60'

PUMP PERFORMANCE CURVE



TOTAL DYNAMIC HEAD CALCULATIONS

- Existing grade at proposed septic tank location is 606' and estimated inlet invert elevation will be 602.4'. The inlet invert elevation is based on 1% fall on the proposed sewer line between the inlet of the existing septic tank (TBA) and the inlet into the proposed septic tank. It is anticipated that the soil cover on top of the proposed septic tank will be 2.35'.
- Existing grade at the pump chamber is 606'. The inlet invert into the pump chamber will be 601.98'. The estimated cover on the pump chamber will be 2.7'
- Pump off float will be 22" above the bottom of the pump chamber, making it 41" below the inlet invert. Consequently, the pump off float elevation is 598.56'.
- Existing grade at the highest trench (Trench 2) is 611.83' and the lateral pipe (invert elevation 609.83') will be 24" below grade; consequently, the distribution lateral will have 24" cover.
- Consequently, the static head is 11.27'.
- Friction loss
  - Length of force main and manifold – 2" fusible HDPE pipe – 388'
  - Equivalent length of fittings
    - 1 ea. 90° ells – 8.6' ea. – 8.6'
    - 8 ea. 45° ells – 2.6' ea. – 20.8'
  - Total Equivalent pipe length – 29.4'
  - Total length of pipe – 417.4'
  - Friction loss for 2" fusible HDPE pipe with a flow of 30 gpm is 1.6'/100' length of pipe. Consequently, pipe friction loss is 6.68'
- Total Dynamic Head is therefore 11.27' + 6.68' = 17.95'
- Pump must be able to deliver a minimum of 30 gpm at a TDH of 17.95'
- Selected Goulds submersible effluent pump Model 3885, series WE0511H, 1/2 Hp, single phase, 115 volts.
- System Operational Curve
  - Using 35 gpm yields 20.44' of TDH
  - Using 40 gpm yields 22.95' of TDH
  - Using 45 gpm yields 25.45' of TDH
  - Using 50 gpm yields 28.79' of TDH
  - System operational point – 45 gpm at 25.45' TDH – 4.4 fps velocity

Approved Septic System Plan  
Howard County Health Department  
1520 gal. Septic Tank and  
1500 gal. Pump Tank and  
Goulds WE0511H Pump or equiv.  
Signature  
1/24/2020  
Date

OWNER/DEVELOPER

KEVIN & MARIA GARVEY  
2605 ROUTE 97  
GLENWOOD, MD 21738  
443-506-5112

NO.	REVISION	DATE
REPAIR OF SEWAGE DISPOSAL PLAN 2605 ROUTE 97 GREEN MEADOWS SUBDIVISION – LOT 8 ZONE: RR-DEO		
TAX MAP: 14, GRID: 11 ELECTION DISTRICT: 4		PARCEL: 217 HOWARD COUNTY, MARYLAND
SEWAGE DISPOSAL SYSTEM DESIGN PREPARED BY JAMES R. POWELL 421 ROCKWAY ROAD CATONSVILLE, MARYLAND 21228 443-860-3189		PROJECT NO.: 4177 DESIGNED BY: JRP DRAWN BY: KTG CHECKED BY: JRP DATE: JAN. 2, 2020
SIGNATURE: <i>James R. Powell</i>		DATE: 1-8-20
SHEET: 2 OF 2		