

8/20/96  
House Conn ASAP

# PERMIT

SEWAGE DISPOSAL SYSTEM

DEPARTMENT OF HEALTH AND MENTAL HYGIENE

P 57016 H

A 44241

DISTRICT 7-8-96

DATE

HOWARD COUNTY HEALTH DEPARTMENT

BUREAU OF ENVIRONMENTAL HEALTH

313-2640

DATE SYSTEM APPROVED 8/20/96

INSPECTOR ALM

INDEXED

South Carroll Backhoe, Inc.

IS PERMITTED TO INSTALL ☒ ALTER

ADDRESS 4410 Salem Bottom Road, Westminster, MD 21157 PHONE 875-4197

SUBDIVISION Gwyndyl Oak Estates LOT 6 ROAD 2821 Rolling Fork Way

PROPERTY OWNER NV Homes / APEI

ADDRESS

SEPTIC TANK CAPACITY 1250 GALLONS

NUMBER OF BEDROOMS 4

210 SQUARE FEET PER BEDROOM

LINEAR FEET OF TRENCH REQUIRED 210

219  
840  
210  
41840

TRENCHES - Trench to be 2 feet wide. Inlet 4 feet below original grade. Bottom maximum depth 8 feet below original grade. Effective area begins at 4 feet below original grade. 4 feet of stone below distribution pipe.

LOCATION - Place distribution box 100 feet off the back (257.78') lot line and 110' off the lot corner at the end of the flagstem. Run trenches on contour in both directions.

NOTES - Maintain at least 100' from the well to the septic tank. No trench to exceed 100 feet in length. Provide 6" - 8" diameter cleanout and cap to grade or above on septic tank.

PLANS APPROVED BY Glen Savage 7-3-96 DATE 7/3/96

COVER NO WORK UNTIL INSPECTED AND APPROVED

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM

NOTE: CLEANOUT REQUIRED EVERY 70 FEET OF SEWER LINE AND/OR AT 90° SWEEPS IN LINES FROM HOUSE TO DRAIN FIELDS, 90° ELBOWS NOT ACCEPTABLE.

NOTE: ALL PARTS OF SEPTIC SYSTEMS (I.E. TANK, DISTRIBUTION BOX TRENCHES) TO BE 100 FEET FROM WELL (UNLESS OTHERWISE SPECIFICALLY AUTHORIZED)

NOTE: IF DEEP TRENCH(ES) ARE USED CALL FOR INSPECTION BEFORE AND AFTER PLACING GRAVEL IN TRENCH(ES)

NOTE: NO DRY WELL SHALL EXCEED 15 FOOT IN DIAMETER NO ABSORPTION TRENCH TO EXCEED 100 FEET IN LENGTH

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON OR SCHEDULE 35/40 PVC OR ABS

PERMIT VOID AFTER TWO YEARS

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL STAND PIPES MUST BE 6 INCHES IN DIAMETER CAST IRON. CONCRETE OR TERRA COTTA OR PVA OR ABS ACCEPTED. IF TOP OF SEPTIC TANK IS DEEPER THAN 3 FEET. MANHOLE TO GRADE REQUIRED.

NOTE: DISTRIBUTION BOXES MUST HAVE BAFFLES

\*INSTALLER IS RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT


HD-260(6-90)

\*CALL 461-9933 FOR INSPECTION OF SEPTIC SYSTEM.

BLDG. PERMIT SIGNED 800129941  
5/2/01-deck w/stairs & gazebos on rear of house  
AND RETURNED 7/26/96  
Serial # B 10/11/281

A 44241

WPI OK  
4' B.G.  
7/16/96 CW  
(FEEZER)



INDICATE NORTH - NAME ADJOINING ROADWAY AS BASE LINE

SEPTIC TANK LEVEL 1250 gal CLEANOUTS STV

DISTRIBUTION BOX LEVEL OK baffles in

DRAIN FIELD/TITLE DEPTH 8.0-8.5 FT. TRENCH WIDTH 2.0 FT. INLET DEPTH 4 FT.

EFFECTIVE GRAVEL DEPTH 4 FT. TOTAL LENGTH 220 FT.

NUMBER OF TRENCHES 4 <sup>(9) 55'</sup> ONE SIDEWALL/BOTTOM AREA 880 SQ. FT.

DRYWALL INSIDE DIAMETER — FT. EFFECTIVE DEPTH BELOW INLET — FT.

ABSORBENT AREA — SQ. FT.

REMARKS: 7/16/96 House connection not made - OK to stone trench 2:3  
and covered. All 7/16/96 4TH TRENCH OK TO COVER. (CW)  
8/20/96 House connection made All

DATE SYSTEM APPROVED 8/20/96 INSPECTOR All

# APPLICATION

PERCOLATION TESTING

A 44241

P \_\_\_\_\_

HOWARD COUNTY HEALTH DEPARTMENT  
BUREAU OF ENVIRONMENTAL HEALTH  
P.O. BOX 476 ELLICOTT CITY, MARYLAND 21043  
TELEPHONE: 461-9933

DISTRICT 4th

DATE \_\_\_\_\_

TO: THE COUNTY HEALTH OFFICER  
ELLICOTT CITY, MARYLAND

I, HEREBY, APPLY FOR THE NECESSARY TEST IN ORDER TO CONSTRUCT (OR RECONSTRUCT) A SEWAGE DISPOSAL SYSTEM.

PROPERTY OWNER Pettit and Griffin, Inc.

ADDRESS 18205-D Flower Hill Way PHONE 301-975-1020  
Gaithersburg, Maryland 20879

PROSPECTIVE BUYER \_\_\_\_\_

ADDRESS \_\_\_\_\_ PHONE \_\_\_\_\_

PROPERTY LOCATION:

SUBDIVISION McKendree Estates LOT NO. 6  
~~3815W8~~

ROAD AND DESCRIPTION McKendree Road and Route 97 (9/15/93)

TAX MAP 14 PARCEL # 123

SIZE OF LOT 3 AC. + TYPE BLDG. Single Family  
(SINGLE FAMILY DWELLING OR COMMERCIAL)

THE SYSTEM INSTALLED UNDER THIS APPLICATION IS ACCEPTABLE ONLY UNTIL PUBLIC FACILITIES BECOME AVAILABLE. I FULLY UNDERSTAND THE

FEE CONNECTED WITH THE FILING OF THIS PERC TEST APPLICATION IS NON-REFUNDABLE UNDER ANY CIRCUMSTANCES. I ALSO AGREE TO COMPLY

WITH ALL M.O.S.H.A. REQUIREMENTS IN TESTING THIS LOT. \_\_\_\_\_

(SIGNATURE OF APPLICANT)

APPROVED BY \_\_\_\_\_ FOR \_\_\_\_\_ DATE \_\_\_\_\_

REJECTED BY \_\_\_\_\_ FOR \_\_\_\_\_ DATE \_\_\_\_\_

HOLD PENDING FURTHER TESTS \_\_\_\_\_ DATE \_\_\_\_\_




REASONS FOR REJECTION OR HOLDING \_\_\_\_\_

HD-216

## THIS IS NOT A PERMIT

REMARKS 1st test 1' drop

| DATE    | TEST NO. | DEPTH | PRE-WET | TEST - 1' DROP | STOP | START | STOP | START | STOP | TIME |
|---------|----------|-------|---------|----------------|------|-------|------|-------|------|------|
| 6/24/93 | 13       | 4     | 107     | 128            | 140  | 112   | 3    | OK    | 11.5 | 13   |
|         | 14       | 7     | 107     | 128            | 140  | 112   | 3    | OK    | 11.5 | 13   |
|         | 15       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 16       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 17       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 18       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 19       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 20       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 21       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 22       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 23       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 24       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 25       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 26       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 27       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 28       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 29       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |
|         | 30       | 11    | 114     | 117            | 117  | 117   | 10   | OK    | 11.5 | 13   |



INDICATE NORTH - NAME ADJOINING ROADWAY AS BASE LINE

Antenna 11 m  
Grass 3 ft

NEW 8  
6/15/93  
11  
10/23  
10/24

**COUNTY#**

## SOIL PROFILE

TOPSOIL  
BROWN CLAY

PINK  
BROWN  
SAND  
LOAN

BEIGE  
SAND  
LOAM


TOP  
SOIL  
CLAY

PULL  
BROWN  
SAND  
LOAM  
& FEW  
COBBLES

TOPSOIL  
CLAY

PINK  
BROWN  
SAMP  
LOAM

BEIGE  
SAND  
LOAM



INDICATE NORTH - NAME ADJOINING ROADWAY AS BASE LINE.

Road A

| DATE                                                                                                                                                                            | TEST NO. | DEPTH     | PRE-WET      |              | TEST - 1" DROP |              | TIME   |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|--------------|--------------|----------------|--------------|--------|
|                                                                                                                                                                                 |          |           | START        | STOP         | START          | STOP         |        |
| 11/13/92                                                                                                                                                                        | 15<br>17 | 4<br>8    | 1206<br>1206 | 1209<br>1209 | 1209<br>1209   | 1211<br>1211 | 3<br>2 |
| 11/13/92                                                                                                                                                                        | 14       | 13        | OK           |              |                |              |        |
| 11/11                                                                                                                                                                           | 25<br>26 | 3.5<br>12 | 1216<br>OK   | 1229         | 1229           | 1242         | 1.3    |
| 11/11                                                                                                                                                                           | 35<br>36 | 5<br>13   | 1217<br>OK   | 1220         | 1220           | 1232         | 12     |
| 11/13/92                                                                                                                                                                        | 4        | 13 1/2    | OK           |              |                |              |        |
| <p>THESE TEST RESULTS ARE FOR LOT (5)</p> <p>LOT 6 HAS TWO HOLES IN COMMON<br/>(#4 &amp; #3); OTHER TEST RECORDS ATTACHED</p> <p><del>NOT AVAILABLE AT THIS TIME (CW)</del></p> |          |           |              |              |                |              |        |

REMARKS

TYPE OF SOIL

TESTED BY

**TRENCH DESIGN DATA: AVERAGE PERCOLATION TIME**

INLET DEPTH

MAXIMUM BOTTOM DEPTH

**ALSO PRESENT**

**TRENCH WIDTH**

SQ. FT./BEDROOM

180

C1 5232 SEQUENCE NO. (DENV USE ONLY)  
(THIS NUMBER IS TO BE PUNCHED IN COLS. 3-6 ON ALL CARDS)

STATE OF MARYLAND  
WELL COMPLETION REPORT  
FILL IN THIS FORM COMPLETELY  
PLEASE PRINT OR TYPE

THIS REPORT MUST BE SUBMITTED WITHIN  
45 DAYS AFTER WELL IS COMPLETED.

COUNTY NUMBER A 44241

ST/CO USE ONLY  
DATE Received  
DATE WELL COMPLETED 030695  
Depth of Well 2200 (TO NEAREST FOOT)  
PERMIT NO. FROM "PERMIT TO DRILL WELL" H0-94-0306

OWNER Pettif & Griffith Inc.  
STREET OR RFD 18215 N Flower Hill Way first name TOWN Gaithersburg 20879  
SUBDIVISION Gwyndyl Oak Estates SECTION LOT 6

WELL LOG  
Not required for driven wells  
STATE THE KIND OF FORMATIONS  
PENETRATED, THEIR COLOR, DEPTH,  
THICKNESS AND IF WATER BEARING

| DESCRIPTION (Use<br>additional sheets if needed) | FEET |     | Check<br>if water<br>bearing |
|--------------------------------------------------|------|-----|------------------------------|
|                                                  | FROM | TO  |                              |
| soft brown dirt                                  | 0    | 58  |                              |
| hard tan/gray rock                               | 58   | 63  |                              |
| med hard tan/gray rock                           | 63   | 79  |                              |
| soft tan rock                                    | 79   | 82  | x                            |
| med hard/hard tan rock                           | 82   | 129 |                              |
| med tan rock                                     | 129  | 130 |                              |
| hard tan/gray rock                               | 130  | 200 | x                            |

GROUTING RECORD  
WELL HAS BEEN GROUTED (Circle Appropriate Box) YES Y NO N  
TYPE OF GROUTING MATERIAL  
CEMENT CM BENTONITE CLAY BC  
NO. OF BAGS 15 NO. OF POUNDS 1600  
GALLONS OF WATER 95  
DEPTH OF GROUT SEAL (to nearest foot)  
from 0 ft. to 62 ft.  
(enter 0 if from surface)

CASING RECORD  
casing types insert appropriate code below  
ST CO STEEL CONCRETE  
PL OT PLASTIC OTHER  
MAIN CASING TYPE  
Nominal diameter top (main) casing (nearest inch) 6  
Total depth of main casing (nearest foot) 63  
S T 6 3

OTHER CASING (if used)  
diameter inch depth (feet) from to  
EACH CASING

SCREEN RECORD  
screen type or open hole insert appropriate code below  
ST BR HO STEEL BRASS OPEN HOLE  
PL OT PLASTIC OTHER  
C2

DEPTH (nearest ft.)  
S T 56 98  
H O 98 200  
S T 56 98  
H O 98 200

SLOT SIZE 1.25 2 3  
DIAMETER OF SCREEN 5 (NEAREST INCH)  
from to

GRAVEL PACK  
IF WELL DRILLED WAS FLOWING WELL INSERT F IN BOX 68

OEP USE ONLY (NOT TO BE FILLED IN BY DRILLER)

T (E.R.O.S.) W Q  
70 72 74 75 76  
TELESCOPE CASING LOG INDICATOR OTHER DATA

PUMPING TEST  
HOURS PUMPED (nearest hour) 3  
PUMPING RATE (gal. per min. to nearest gal.) 94  
METHOD USED TO MEASURE PUMPING RATE timer  
WATER LEVEL (distance from land surface)  
BEFORE PUMPING 35  
WHEN PUMPING 22  
TYPE OF PUMP USED (for test)  
A air P piston T turbine  
C centrifugal R rotary O other (describe below)  
J jet S submersible

PUMP INSTALLED  
DRILLER WILL INSTALL PUMP YES NO  
IF DRILLER INSTALLS PUMP, THIS SECTION MUST BE COMPLETED FOR ALL WELLS EXCEPT HOME USE  
TYPE OF PUMP INSTALLED PLACE (A,C,J,P,R,S,T,O) IN BOX - SEE ABOVE: 29  
CAPACITY: GALLONS PER MINUTE (to nearest gallon) 31 35  
PUMP HORSE POWER 37 41  
PUMP COLUMN LENGTH (nearest ft.) 43 47  
CASING HEIGHT (circle appropriate box and enter casing height)  
+ above LAND SURFACE 1 (nearest foot)  
- below

LOCATION OF WELL ON LOT  
SHOW PERMANENT STRUCTURE SUCH AS BUILDING, SEPTIC TANKS, AND/OR LANDMARKS AND INDICATE NOT LESS THAN TWO DISTANCES (MEASUREMENTS TO WELL)  
70' LPL  
281' RPL

CIRCLE APPROPRIATE LETTER  
A A WELL WAS ABANDONED AND SEALED WHEN THIS WELL WAS COMPLETED  
E ELECTRIC LOG OBTAINED  
P TEST WELL CONVERTED TO PRODUCTION WELL

I HEREBY CERTIFY THAT THIS WELL HAS BEEN CONSTRUCTED IN ACCORDANCE WITH COMAR 26.04.04 "WELL CONSTRUCTION" AND IN CONFORMANCE WITH ALL CONDITIONS STATED IN THE ABOVE CAPTIONED PERMIT, AND THAT THE INFORMATION PRESENTED HEREIN IS ACCURATE AND COMPLETE TO THE BEST OF MY KNOWLEDGE.

DRILLERS IDENT. NO. 304  
DRILLERS SIGNATURE  
SITE SUPERVISOR (sign. of driller or journeyman responsible for sitework if different from permittee)

HOWARD COUNTY HEALTH DEPARTMENT  
Bureau of Environmental Health  
3525-H Ellicott Mills Drive  
Ellicott City, MD 21043  
Fax 313-2648 313-2640

PLEASE INSPECT  
7-18-96 7/18/96  
COVERED AT TIME OF  
INSPECTION

APPLICATION FOR PITLESS ADAPTER, WELL PUMP AND PRESSURE TANK INSTALLATION

New Installation ☒  
Replacement ☐

Receipt #  
Date 7/17/96

Name of Installer ROBERT L. FEEZER CO., INC. Telephone 795-1401

License Number 2122  
Certified Well Pump Installer ☒

Well Driller ☐ Registered Plumber ☒

Name of Property Owner W. H. Hovick Telephone 791-4657  
Subdivision McKENNEDY EST. Lot # 6 Well Tag # HO-24-0306  
Site Address 2821 Rolling Park Way

Pump

1. Type

- a. Deep well jet ☐  
b. Shallow well jet ☐  
c. Submersible ☒

2. Make STARITE

3. Model # 10P4P02T-02

4. Capacity 10 GPM

5. Pump exceeds well capacity Yes ☐ No ☒

6. If Yes, is low pressure cutoff switch installed? Yes ☐ No ☐

7. What methods are used to protect the pump and electrical wiring from vibrations? Torque arrestors ☐ Cable guards ☒ Other ☐

Motor

1. Horsepower 3/4

2. RPM 3450

3. Voltage ☐

a. 110 ☐

b. 220 ☒

Pitless Adapter

1. Make HANVILL

2. Model # VT800

3. Depth 42"

Tank

1. Capacity 36 GALS.

2. Pressure relief valve? YES

Piping

1. Type POLY

2. Size 1"

3. NSF and/or BOCA

Code approved YES

4. Depth of supply

line 42

Well data

1. Depth 200 ft.

2. Yield 11.25 GPM

3. Static water

level ☐ ft.

4. Will water supply

be disinfected by

installer? YES


I understand that it is my responsibility to notify the Howard County Health Department when the installation is ready for inspection (otherwise this permit is null and void).

All information given above is true to the best of my knowledge.


Signature of Applicant: Robert L. Feezer

Date: 7/17/96


Note: A sticker indicating approval/status of the installation will be placed on the well casing at the time of the inspection.



LOT 11  
A-4853C



BUILDING SETBACKS (B.R.L.'s) SHOWN HEREON PER PLAT No. 11549  
 SETBACK DISTANCES SHOWN HEREON AS "±" HAVE AN ACCURACY OF ±1 FOOT.



7/26/96  
 Proposed propane tank  
 location will have no  
 impact to existing well  
 or septic. OK to proceed

Amy McMiller

△

7/2/96  
Date

Approved Septic System  
Howard County Health Department  
BP 61510

Mark E. Rifkin  
Signature

LOT 6

LOT 5

LOT 4

LOT 3

LOT 2

LOT 1

LOT 0

LOT -1

LOT -2

LOT -3

LOT -4

LOT -5

LOT -6

LOT -7

LOT -8

LOT -9

LOT -10

LOT -11

LOT -12

LOT -13

LOT -14

LOT -15

LOT -16

LOT -17

LOT -18

LOT -19

LOT -20

LOT -21

LOT -22

LOT -23

LOT -24

LOT -25

LOT -26

LOT -27

LOT -28

LOT -29

LOT -30

LOT -31

LOT -32

LOT -33

LOT -34

LOT -35

LOT -36

LOT -37

LOT -38

LOT -39

LOT -40

LOT -41

LOT -42

LOT -43

LOT -44

LOT -45

LOT -46

LOT -47

LOT -48

LOT -49

LOT -50

LOT -51

LOT -52

LOT -53

LOT -54

LOT -55

LOT -56

LOT -57

LOT -58

LOT -59

LOT -60

LOT -61

LOT -62

LOT -63

LOT -64

LOT -65

LOT -66

LOT -67

LOT -68

LOT -69

LOT -70

LOT -71

LOT -72

LOT -73

LOT -74

LOT -75

LOT -76

LOT -77

LOT -78

LOT -79

LOT -80

LOT -81

LOT -82

LOT -83

LOT -84

LOT -85

LOT -86

LOT -87

LOT -88

LOT -89

LOT -90

LOT -91

LOT -92

LOT -93

LOT -94

LOT -95

LOT -96

LOT -97

LOT -98

LOT -99

LOT -100

LOT -101

LOT -102

LOT -103

LOT -104

LOT -105

LOT -106

LOT -107

LOT -108

LOT -109

LOT -110

LOT -111

LOT -112

LOT -113

LOT -114

LOT -115

LOT -116

LOT -117

LOT -118

LOT -119

LOT -120

LOT -121

LOT -122

LOT -123

LOT -124

LOT -125

LOT -126

LOT -127

LOT -128

LOT -129

LOT -130

LOT -131

LOT -132

LOT -133

LOT -134

LOT -135

LOT -136

LOT -137

LOT -138

LOT -139

LOT -140

LOT -141

LOT -142

LOT -143

LOT -144

LOT -145

LOT -146

LOT -147

LOT -148

LOT -149

LOT -150

LOT -151

LOT -152

LOT -153

LOT -154

LOT -155

LOT -156

LOT -157

LOT -158

LOT -159

LOT -160

LOT -161

LOT -162

LOT -163

LOT -164

LOT -165

LOT -166

LOT -167

LOT -168

LOT -169

LOT -170

LOT -171

LOT -172

LOT -173

LOT -174

LOT -175

LOT -176

LOT -177

LOT -178

LOT -179

LOT -180

LOT -181

LOT -182

LOT -183

LOT -184

LOT -185

LOT -186

LOT -187

LOT -188

LOT -189

LOT -190

LOT -191

LOT -192

LOT -193

LOT -194

LOT -195

LOT -196

LOT -197

LOT -198

LOT -199

LOT -200

LOT -201

LOT -202

LOT -203

LOT -204

LOT -205

LOT -206

LOT -207

LOT -208

LOT -209

LOT -210

LOT -211

LOT -212

LOT -213

LOT -214

LOT -215

LOT -216

LOT -217

LOT -218

LOT -219

LOT -220

LOT -221

LOT -222

LOT -223

LOT -224

LOT -225

LOT -226

LOT -227

LOT -228

LOT -229

LOT -230

LOT -231

LOT -232

LOT -233

LOT -234

LOT -235

LOT -236

LOT -237

LOT -238

LOT -239

LOT -240

LOT -241

LOT -242

LOT -243

LOT -244

LOT -245

LOT -246

LOT -247

LOT -248

LOT -249

LOT -250

LOT -251

LOT -252

LOT -253

LOT -254

LOT -255

LOT -256

LOT -257

LOT -258

LOT -259

LOT -260

LOT -261

LOT -262

LOT -263

LOT -264

LOT -265

LOT -266

LOT -267

LOT -268

LOT -269

LOT -270

LOT -271

LOT -272

LOT -273

LOT -274

LOT -275

LOT -276

LOT -277

LOT -278

LOT -279

LOT -280

LOT -281

LOT -282

LOT -283

LOT -284

LOT -285

LOT -286

LOT -287

LOT -288

LOT -289

LOT -290

LOT -291

LOT -292

LOT -293

LOT -294

LOT -295

LOT -296

LOT -297

LOT -298

LOT -299

LOT -300

LOT -301

LOT -302

LOT -303

LOT -304

LOT -305

LOT -306

LOT -307

LOT -308

LOT -309

LOT -310

LOT -311

LOT -312

LOT -313

LOT -314

LOT -315

LOT -316

LOT -317

LOT -318

LOT -319

LOT -320

LOT -321

LOT -322

LOT -323

LOT -324

LOT -325

LOT -326

LOT -327

LOT -328

LOT -329

LOT -330

LOT -331

LOT -332

LOT -333

LOT -334

LOT -335

LOT -336

LOT -337

LOT -338

LOT -339

LOT -340

LOT -341

LOT -342

LOT -343

LOT -344

LOT -345

LOT -346

LOT -347

LOT -348

LOT -349

LOT -350

LOT -351

LOT -352

LOT -353

LOT -354

LOT -355

LOT -356

LOT -357

LOT -358

LOT -359

LOT -360

LOT -361

LOT -362

LOT -363


LOT -364

LOT -365


LOT -366

BASEMENT FLOOR AREA = 615.82'  
INV. OUT OF HOUSE = 620.50' HUNG SEWER  
INV. IN AT SEPTIC TANK = 620.00'  
INV. OUT AT SEPTIC TANK = 619.75'  
EX. ELEV. AT SEPTIC TANK = 619.0'±  
PROP. ELEV. AT SEPTIC TANK = 621'±  
INV. IN AT DIST. BOX = 615.3'  
EX. ELEV. AT DIST. BOX = 619.3'±

TRENCH LENGTH  
DETERMINED BY  
HEALTH DEPT.



TO  
ROLLING  
FORK WAY





---

HOWARD COUNTY HEALTH DEPARTMENT

---

*Joyce M. Boyd, M.D., County Health Officer*

December 18, 1996

Ms. Apel  
2821 Rolling Fork Way  
Glenwood, Maryland 21738

RE: Site Inspection Request for  
Septic Installation Confirmation  
at 2817 Rolling Fork Way

Dear Ms. Apel:

In response to your request for confirmation of the location of the installed septic system at 2817 Rolling Fork Way (Gwyndyl Oak Estates, Lot #5), please find enclosed a copy of the septic installation record, and a copy of the septic contractor's record.

Upon review of this information and after field confirmation, I hereby affirm that the installed septic system on Lot #5 is greater than 100 (one hundred) feet from your existing well.


Please review the enclosed documents. If you have any other questions or concerns, please contact me at the address below or by calling (410) 313-2640.

Sincerely,

Donna K. Soe, R.S.  
Water and Sewerage Program

Enclosure  
DKS  
cc: file

William A. Lloyd James Esq



**PARCEL 'A'**

N 87°13'07" E 257.78'  
S 02°31'35" E 333.16'  
N 02°31'35" W 166.40'  
S 56°00'00" E 343.31'  
N 56°00'00" W 359.07'  
S 84°00'00" W 221.99'

PVI  
SE W RAGE  
L S M I

ROLLING FORK WAY  
50 FT W/W

R = 925.00'  
L = 12.00'

10' PUBLIC TRIF  
MAINTENANCE EASEMENT

**INSET**  
SCALE 1"=150'

ASPHALT DRIVE  
166.40'

S 56°00'00" E 343.31'  
N 56°00'00" W 359.07'

2021 DOLLING FORK WAY

|                                                                                                                                                                                                  |                                                   |                                          |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------|------------------------------------------|
| DEPARTMENT OF INSPECTIONS, LICENSES AND PERMITS<br>3430 COURT HOUSE DRIVE<br>ELICOTT CITY, MD 21043<br>PERMITS (410) 313-2455 INSPECTIONS (410) 313-1810<br>AUTOMATED INFORMATION (410) 313-3300 | <b>HOWARD COUNTY</b><br><b>PERMIT APPLICATION</b> | <b>PERMIT NUMBER</b><br><u>B00129941</u> |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------|------------------------------------------|

|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Building Address <u>2821 Rolling Fork Way</u><br><u>Glenwood Md 21738</u><br><br>Suite/Apt. #: _____ SDP/WP/Petition #: _____<br>Census Tract <u>14</u> Subdivision <u>Gumpkyl Oak Est</u><br>Section <u>8</u> Area _____ Lot <u>6</u><br>Tax Map <u>14</u> Parcel <u>123</u> Grid <u>11</u><br>Zoning <u>RC</u> Map Coordinates <u>7D3</u> Lot size _____<br><br>Existing Use <u>SFO</u><br>Proposed Use <u>SFO with deck</u><br>Estimated Construction Cost <u>\$ 10,200.00</u><br>Description of Work <u>Construct a deck with</u><br><u>stairs and fence on rear of house.</u><br><u>28x20 12 ft. x 6 ft.</u><br>Occupant or Tenant <u>JAMES + PATRICIA APEL</u><br>Contact Name <u>SAME</u><br>Address <u>2821 Rolling Fork Way</u><br>City <u>Glenwood</u> State <u>Md</u> Zip Code <u>21738</u><br>Phone <u>410-489-9944</u> Fax _____ | Property Owner's Name <u>JAMES + PATRICIA APEL</u><br>Address <u>2821 Rolling Fork Way</u><br>City <u>Glenwood</u> State <u>Md</u> Zip Code <u>21738</u><br>Home Phone <u>410-489-9944</u> Work Phone _____<br>Applicant's Name & Mailing Address, (if other than stated herein): _____<br><br>Phone _____ Fax _____<br><br>Contractor Company <u>A.R.C. BUILDERS INC</u><br>Contact Person <u>REGAN J. COLLIER</u><br>Address <u>1003 LAOY CAMAREN CT</u><br>City <u>MT. AIRY</u> State <u>Md</u> Zip Code <u>21771</u><br>License No. <u>34204</u> Phone <u>410-489-3606</u> Fax <u>SALES</u><br>Engineer or Architect Company <u>NA</u><br>Contact Person _____<br>Address _____<br>City _____ State _____ Zip Code _____<br>Phone _____ Fax _____ |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

| BUILDING DESCRIPTION - <u>COMMERCIAL</u>                                                                                                                                                                                                                                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | BUILDING DESCRIPTION - <u>RESIDENTIAL</u>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Building Characteristics</b><br>Height: _____<br>No. of stories: _____<br>Gross area, sq. ft. per floor: _____<br>Use group: _____<br>Construction type:<br><input type="checkbox"/> Reinforced Concrete<br><input type="checkbox"/> Structural Steel<br><input type="checkbox"/> Masonry<br><input checked="" type="checkbox"/> Wood Frame<br><input type="checkbox"/> State Certified Modular | <b>Utilities</b><br>Water Supply:<br><input type="checkbox"/> Public<br><input checked="" type="checkbox"/> Private<br>Sewage Disposal:<br><input type="checkbox"/> Public<br><input checked="" type="checkbox"/> Private<br>Electric: Yes <input checked="" type="checkbox"/> No <input type="checkbox"/><br>Gas: Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Propane<br>Heating System:<br><input type="checkbox"/> Electric <input type="checkbox"/> Oil <input type="checkbox"/><br><input type="checkbox"/> Natural Gas <input checked="" type="checkbox"/> Propane Gas<br>Sprinkler system: N/A <input type="checkbox"/><br><input type="checkbox"/> Full <input type="checkbox"/> Partial<br><input type="checkbox"/> Other Suppression<br><input type="checkbox"/> # of Heads | <b>Building Characteristics</b><br>SF Dwelling <input checked="" type="checkbox"/> SF Townhouse <input type="checkbox"/><br><u>Depth</u> <u>Width</u><br>1st floor: _____<br>2nd floor: _____<br>Basement: _____<br>Finished Basement <input type="checkbox"/> Unfinished Basement <input type="checkbox"/><br>Crawl space <input type="checkbox"/> Slab on Grade <input type="checkbox"/><br>No. of Bedrooms: _____<br>Multi-family dwellings:<br>No. of efficiency units: _____<br>No. of 1 BR units: _____<br>No. of 2 BR units: _____<br>No. of 3 BR units: _____<br>Other Structure: _____<br>Dimensions: <u>As to Plan</u><br>Footings: _____<br>Roof: _____<br><input type="checkbox"/> State Certified Modular<br><input type="checkbox"/> Manufactured Home | <b>Utilities</b><br>Water Supply:<br><input type="checkbox"/> Public<br><input checked="" type="checkbox"/> Private<br>Sewage Disposal:<br><input type="checkbox"/> Public<br><input checked="" type="checkbox"/> Private<br>Electric: Yes <input checked="" type="checkbox"/> No <input type="checkbox"/><br>Gas: Yes <input checked="" type="checkbox"/> No <input type="checkbox"/><br>Heating System:<br><input type="checkbox"/> Electric <input type="checkbox"/> Oil <input type="checkbox"/><br><input type="checkbox"/> Natural Gas <input type="checkbox"/><br><input checked="" type="checkbox"/> Propane Gas<br>Sprinkler system: N/A <input type="checkbox"/><br><input type="checkbox"/> NFPA #13D<br><input type="checkbox"/> NFPA #13R<br><input type="checkbox"/> Other: |

THE UNDERSIGNED HEREBY CERTIFIES AND AGREES AS FOLLOWS: (1) THAT HE/SHE IS AUTHORIZED TO MAKE THIS APPLICATION; (2) THAT THE INFORMATION IS CORRECT; (3) THAT HE/SHE WILL COMPLY WITH ALL REGULATIONS OF HOWARD COUNTY WHICH ARE APPLICABLE THEREIN; (4) THAT HE/SHE WILL PERFORM NO WORK ON THE ABOVE REFERENCED PROPERTY NOT SPECIFICALLY DESCRIBED IN THIS APPLICATION; (5) THAT HE/SHE GRANTS COUNTY OFFICIALS THE RIGHT TO ENTER ONTO THIS PROPERTY FOR THE PURPOSE OF INSPECTING THE WORK PERMITTED AND POSTING NOTICES.

|                                                                                                 |                                                                |
|-------------------------------------------------------------------------------------------------|----------------------------------------------------------------|
| <u>Reg. J. Collier</u><br>Applicant's Signature<br><u>A.R.C. BUILDERS INC.</u><br>Title/Company | <u>Regan J. Collier</u><br>Print Name<br><u>9/2/01</u><br>Date |
|-------------------------------------------------------------------------------------------------|----------------------------------------------------------------|

Checks payable to: DIRECTOR OF FINANCE OF HOWARD COUNTY  
 \*\* PLEASE WRITE NEATLY AND LEGIBLY. \*\*  
 - FOR OFFICE USE ONLY -

|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                                                                                                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                                                                                                                                                                                                                                          |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>AGENCY</b><br><input checked="" type="checkbox"/> Land Development DPZ<br><input checked="" type="checkbox"/> State Highways<br><input checked="" type="checkbox"/> Building Official<br><input checked="" type="checkbox"/> Dev. Engineering DPZ<br><input checked="" type="checkbox"/> Health<br><input checked="" type="checkbox"/> Fire Protection<br>Is Sediment Control approval required prior to issuance?<br>YES <input type="checkbox"/> NO <input checked="" type="checkbox"/> | <b>SIGNATURE APPROVAL</b><br><u>5/2/01</u><br><u>Mark Reppert</u><br>CONTINGENCY CONSTRUCTION START: <input type="checkbox"/><br>ONE STOP SHOP: <input type="checkbox"/> | <b>DEPT. SETBACK INFORMATION</b><br>Front: _____<br>Rear: _____<br>Side: _____<br>Side St.: _____<br>All minimum setbacks met? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/><br>Is Entrance Permit required? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/><br>Historic District? YES <input type="checkbox"/> NO <input checked="" type="checkbox"/><br>Lot Coverage for New Town Zone _____<br>SDP/Red-line approval date _____ Accepted by <u>[Signature]</u> | <b>PROPERTY ID#</b> <u>16822</u><br>Filing fee \$ _____<br>Permit fee \$ <u>30</u><br>Excise tax \$ _____<br>Sub-total paid \$ _____<br>Add'l permit fee \$ _____<br>TOTAL FEES \$ <u>30</u><br>Balance due \$ _____<br>Check # <u>1099</u><br>Validation # <u>23415</u> |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|