

PERMIT

SEWAGE DISPOSAL SYSTEM

DEPARTMENT OF HEALTH AND MENTAL HYGIENE

HOWARD COUNTY HEALTH DEPARTMENT

BUREAU OF ENVIRONMENTAL HEALTH

461-9933

INDEXED

P 47924

A REPAIR

DISTRICT

DATE 3/18/92

DATE SYSTEM APPROVED 3/16/92

INSPECTOR RH

DAVID BROWNE TANK 4/16/92

Jack Fyock

- TRENCHES 3/16/92

IS PERMITTED TO INSTALL ALTER X

ADDRESS DAVID BROWNE - TANK REPLACEMENT 4/16/92 PHONE 988-9270

SUBDIVISION LOT ROAD 13160 Triadelphia Road

PROPERTY OWNER Bertha Burgess

13160 Triadelphia Road

ADDRESS Ellicott City, Maryland

SEPTIC TANK CAPACITY 3 GALLONS

BUILDING PERMIT No. 41252

NUMBER OF BEDROOMS 3

125 SQUARE FEET PER BEDROOM

LINEAR FEET OF TRENCH REQUIRED 47

4/10/92 - REQUEST RECEIVED TO
REPLACE EXISTING TANK.
OK - SAME PERMIT. CWI

REPAIR - PURPOSE - REPAIR FAILING SEPTIC SYSTEM AND TO ESTABLISH FUTURE REPAIR AREA NOT
IN CONFLICT WITH POOL LOCATION.
Call for inspection when ground is opened so sanitarian can recommend
repair. 3/06/92

3/16/92 - TRENCH 11 FT DEEP, INLET 3 FT DEEP
8 FT STONE PUT NEW TRENCH BETWEEN THE OLD TRENCH
& THE TANK & LEAVE THE OLD TRENCH CONNECTED TO THE TANK RH

PLANS APPROVED BY DATE

COVER NO WORK UNTIL INSPECTED AND APPROVED

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM

NOTE: CLEANOUT REQUIRED EVERY 70 FEET OF SEWER LINE AND/OR AT 90° SWEEPS IN LINES FROM HOUSE TO DRAIN FIELDS, 90° ELBOWS NOT ACCEPTABLE.

NOTE: ALL PARTS OF SEPTIC SYSTEMS (I.E. TANK, DISTRIBUTION BOX TRENCHES) TO BE 100 FEET FROM WELL (UNLESS OTHERWISE SPECIFICALLY AUTHORIZED)

NOTE: IF DEEP TRENCH(ES) ARE USED CALL FOR INSPECTION BEFORE AND AFTER PLACING GRAVEL IN TRENCH(ES)

NOTE: NO DRY WELL SHALL EXCEED 15 FOOT IN DIAMETER NO ABSORPTION TRENCH TO EXCEED 100 FEET IN LENGTH

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON OR SCHEDULE 35/40 PVC OR ABS

BLDG. PERMIT SIGNED

AND RETURNED 3/16/92

PERMIT VOID AFTER TWO YEARS

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL STAND PIPES MUST BE 6 INCHES IN DIAMETER CAST IRON. CONCRETE OR TERRA COTTA OR PVA OR ABS ACCEPTED. IF TOP OF SEPTIC TANK IS DEEPER THAN 3 FEET. MANHOLE TO GRADE REQUIRED.

NOTE: DISTRIBUTION BOXES MUST HAVE BAFFLES

*INSTALLER IS RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT

47924

