

P518620-C

10/26/76

PERMIT INDEXED

F
23373

A 20933

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

ELLICOTT CITY

NOT FOUND

DISTRICT 403

DATE 6/2/76

Charles R. Starbough

X

IS PERMITTED TO INSTALL ALTER

ADDRESS Timonium, Maryland

PHONE 756-2383

A SEWAGE DISPOSAL SYSTEM LOCATED AT

SUBDIVISION

ROAD 15000 Woodbine-Maryland Rd.

PROPERTY OWNER Simon H. Davis

ADDRESS Route 2, Box 24, Marriottsville, Md. 21104

PHONE: 796-2967

SPECIFICATIONS 3 bedrooms

DRAIN FIELD DEPTH FEET, BOTTOM AREA SQ. FT.

SEEPAGE PITS ABSORBENT SIDE-WALL AREA SQ. FT.

SEPTIC TANK CAPACITY 1000 GALLONS

FOR GARAGE GRINDER, INCREASE DISPOSAL AREA AND TANK CAPACITY SEE.

OTHER DRY WELL - To have 125 sq. ft. effective absorbent sidewall area per bedroom below inlet. Inlet to be 4 ft. below original grade and maximum depth 12 ft. below original grade. Locate dry well 150 ft. from front property line and 20 ft. off left property line when facing lot from Woodbine-Maryland Road. (See Note 1 & 2).

NOTE: ALL PIPE FROM HOUSE TO DISPOSAL AREA MUST BE CAST IRON. PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAIN PIPE ON SEPTIC TANK AND DRY WELL. SEWER PIPES MUST BE 6 INCHES IN DIAMETER. CAST IRON, CONCRETE OR TERRA COTTA ACCEPTED.

PLANS APPROVED BY Charles B. Streaker

DATE 1/7/75

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER HO HOLES UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

A 20933

P518620-C

