

7/11/77  
7/12/77  
7/13/77 - 011  
9:15 a.m.  
7/8/77  
7/9/77

# PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

P 26232

A 18308

ELLICOTT CITY

DISTRICT 3rd

DATE 6/28/77

**INDEXED**

Roland Barbh

IS PERMITTED TO INSTALL  ALTER

ADDRESS Clarksville Pike, Ellicott City, Md. PHONE 730-8495

A SEWAGE DISPOSAL SYSTEM LOCATED AT \_\_\_\_\_

SUBDIVISION Egles Loft ROAD 13128 Williamfield Drive LOT 23

PROPERTY OWNER Nu Homes, Inc.

ADDRESS 6655-II Dobbin Road, Columbia, Md. 21045 Phone: 997-7019

SPECIFICATIONS 4 bedrooms

DRAIN FIELD \_\_\_\_\_ DEPTH \_\_\_\_\_ FEET, BOTTOM AREA \_\_\_\_\_ SQ. FT.

SEEPAGE PITS \_\_\_\_\_ ABSORBENT SIDE-WALL AREA \_\_\_\_\_ SQ. FT.

SEPTIC TANK CAPACITY 1250 GALLONS

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 22% & TANK CAPACITY 50%.

OTHER - DRY WELL AND TRENCH - Dry well to have ~~128~~<sup>250</sup> sq. ft. sidewall area, Inlet at 4 ft. and maximum depth 11 ft. below original grade. Locate dry well 25 ft. from left lot line and 100 ft. from edge of Williamfield Drive as seen when facing lot from Williamfield Drive. Trench to be 36 ft. long for a total sidewall area of 152 sq. ft. Run trench off right side of dry well, toward right lot line, as seen when facing lot from Williamfield Drive. Keep trench on level contour. NOTE: CALL FOR INSPECTION OF TRENCH BEFORE PLACING STONE IN TRENCH. NOTE: ALL PIPE FROM HOUSE TO DISPOSAL AREA MUST BE CAST IRON. PERMIT VOID AFTER THREE YEARS. NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL. STAND PIPES MUST BE 6 INCHES IN DIAMETER, CAST IRON, CONCRETE OR TERRA COTTA ACCEPTED. NOTE: NO DRY WELL IS TO EXCEED 15 FOOT IN DIAMETER.

PLANS APPROVED BY William W. Zepp DATE 2/18/76

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

18308



INDICATE NORTH. NAME ADJOINING ROADWAY AS BASE LINE.

*William Circle Drive*

PERMIT CARD  signed final O.K. *F.S.*

SEPTIC TANK, LEVEL  CLEANOUTS  S.T.  D.W.

DISTRIBUTION BOX, LEVEL *n.o.*

TILE FIELD, DEPTH 12 FT. TRENCH WIDTH 2 FT.

GRAVEL DEPTH 8-8 1/2 IN. TOTAL LENGTH 32 FT.

NUMBER OF TRENCHES 1 <sup>1/2 SIDEWALL</sup> TOTAL BOTTOM AREA 224 ~~sq~~

SEEPAGE PITS, INSIDE DIAMETER 4.4 FT. DEPTH BELOW INLET 7' effective FT.

Drywell ABSORBENT AREA 308 SQ. FT. Total abs. area 532 ~~sq~~

REMARKS 7/12/77 O.K. to put normal depth in trench F.S.

7/13/77 O.K. to cover system F.S.

DATE SYSTEM APPROVED 7/13/77 INSPECTOR Frank Skinner

