

## **Bureau of Environmental Health**

8930 Stanford Boulevard, Columbia, MD 21045 Main: 410-313-2640 | Fax: 410-313-2648 TDD 410-313-2323 | Toll Free 1-866-313-6300 www.hchealth.org

Facebook: www.facebook.com/hocohealth

Maura J. Rossman, M.D., Health Officer

RECEIPT DATE: 4-16-15 ONSITE SEWAGE DISPOSAL	. SYSTEM P 555814
INSTALLATION APPROVAL DATE: 7/9/15 Your CONSTRUCTION	Α
PROPERTY ADDRESS: 14905 Victory Lane	
SUBDIVISION: Merwether Farm	LOT: 1 TAX ID: (1) 1593610
CONTRACTOR: Fogle's Septic Clean Inc.	EMAIL: kevin@foglesinc.com
CONTRACTOR ADDRESS: 580 Obrecht Road, Sykesville, MD 21784	PHONE: <b>410-795-5670</b>
PROPERTY OWNER: Toll Brothers Inc.	EMAIL:
OWNER ADDRESS: 14881 Meriwether Drive, Glenelg, MD 21737	PHONE: 301-418-1923
BAT UNIT MODEL: NOTICE THAT P 500 PUMP SIZE:	PUMP TANK CAPACITY: 500GPD
DISTRIBUTION SYSTEM: GRAVITY  LOW PRESSURE DOSED	NUMBER OF BEDROOMS:
LINEAR FEET REQUIRED: 222	INLET DEPTH: SEE BAT PLAN 5'
TRENCHES: TRENCH WIDTH: 3	MAXIMUM BOTTOM DEPTH: \$ 7.5'
MINIMUM SPACE BETWEEN TRENCHES: 10 EFFECT	TIVE AREA BEGINNING DEPTH: 5,5-6'
LOCATION: PER APPROVED SITE PLAN. SEWAGE DISPOSAL AREA AND BAT SURVEYOR PRIOR TO PRE-CONSTRUCTION INSPECTION.	UNIT LOCATION MUST BE STAKED BY LICENSED
Install BAT Unit per plan.	
NOTES: 3 x 74'	
ISSUED BY: Hank Oswald ISSUE DATE: 4	-2215 EXPIRATION DATE: 4-22-16
NOTE: CONTRACTOR MUST SCHEDULE A PRE-CONSTRUCTION INSPECTION P	RIOR TO BEGINNING ANY INSTALLATION
NOTE: CONTRACTOR MUST SCHEDULE AN INSPECTION AND GAIN APPROVAL	
NOTE: STONE MUST BE APPROVED BY HEALTH DEPARTMENT AND GRAVEL TIC	CKET MUST BE AVAILABLE FOR REVIEW.
NOTE: WATERTIGHT SEPTIC TANKS REQUIRED  NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE AT LEAST 100 FEET DOWNGRAI	DIENT FROM ANY WATER WELL
NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAME	
NOTE: AN ELECTRICAL PERMIT IS REQUIRED FOR INSTALLATION OF ANY ELECTRICAL PERMIT IS REPORTED FOR INSTA	
DURING BAT INSTALLATION.  NOTE: MDE RECOMMENDS SEPTIC TANKS, BAT, AND OTHER PRETREATMENT TO ENGUES THAT COURSE ARE NOT DISCHARGED TO THE DISCHARGED TO THE DISCHARGED TO THE DISCHARGED TO THE DISCHARGED.	
TO ENSURE THAT SOLIDS ARE NOT DISCHARGED TO THE DISPOSAL AR	


NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT.

CALL 410-313-1771 TO SCHEDULE INSPECTIONS.

· · · · · · · · · · · · · · · · · · ·	
NOT TO SCALE	TRENCH/DRAINFIELD DATA
	WIDTH INLET BOTTOM
	NUMBER OF TRENCHES 3
	TOTAL LENGTH 219'
	ABSORPTION AREA 651'+510EWAL
	DISTRIBUTION BOX LEVEL YES
	DISTRIBUTION BOX BAFFLE VES
	DISTRIBUTION BOX PORT YES
	SEPTIC TÂNK DATA
·	SEPTIC TANK I LEVEL
	MANUFACTURER BACKRIVER
	CAPACITY 1300 GAL
See separate sheet for as-built drawing	SEAM LOC TOP
	TANK LID DEPTH 1
as-built drawing	BAFFLES NO BAFFLE FILTER NO
3/	MANHOLE LOC FRONT, MID REAR
	6" PORT LOC NO NE
	WATERTIGHT TEST No
	SLOTTED_No
	DATE ON LID NO NE
	PUMP/SEPTIC TANK LEVEL
	MANUFACTURER
	CAPACITYGAL
* *	SEAMLOC
,	TANK LID DEPTH BAFFLES
	BAFFLE FILTER
	MANHOLE LOC
·	6" PORTLOC
•	WATERTIGHT TEST
DO AD MANTE	DATE ON LID
ROAD NAME	DATE ON LID
PRE-CONSTRUCTION:	
5/4/2015	
	<del></del>
INSTALLATION: 5/5/15 House connection not yet made- pipe laid	most of the way from
house to tank location. Fogle's on site digging tank hole f	
	0
5/6/15 Il finished open at ends. Currently digging TZ. 4.5'	
5/6/15 T2 and T3 finished; T2 open at ends and T3	
from Doox to trenches laid Need to level speed levele	rs in D-bax. (C) 5/8/15
Leveled speed levelers in D-box. Need BAT startup certil	fication (SC)
FINAL INSPECTOR L. Wash. DATE OF APPROVA	1 7/0/1-
FINAL INSPECTOR DATE OF APPROVA	· ////-

-



# Back River Pre-Cast, LLC

PO BOX 329 Glyndon, MD 21071 Phone # 410-833-3394 Fax # 410-833-4116

# Letter of Certification

This is to certify that the Norweco Singulair TNT 600 GPD Septic Tank installed at 14905 Victory Ln., Glenelg, MD 21737 was installed on May 5, 2015 according to the manufacture's specifications.

Installer: Matthew Cooney


Property Owner: Toll MD VIII Limited Partnership


MATTHEW GECKLE

Vice-President

EASTERN DIVISION 60%

COPTRIGHTS 2014 TOLL BROTHERS, DIC.





## Oswald, Hank

From:

Sent:

Monday, December 22, 2014 11:30 AM

To:

Oswald, Hank

Subject:

Fwd: Cattail: Lot #1 Blue Prints

**Attachments:** 

Lot001-A1.pdf; Lot001-A2.pdf; Lot001-A3.pdf

Please find floor plans for lot 1 Steve Landoll

----- Forwarded message -----

From: "Michael Martin" < MMARTIN3@tollbrothersinc.com>

Date: Dec 22, 2014 11:24 AM Subject: Cattail: Lot #1 Blue Prints

Cc:


Michael C. Martin

Cattail Overlook

Office: 410.489.7408

Fax: 410.489.2676





# Oswald, Hank

From:

Oswald, Hank

Sent:

Monday, January 05, 2015 11:40 AM

To:

'Steve Landoll'

Cc: Subject: 'mmartin3@tollbrothersinc.com' Meriwether Farm Lots 1, 4, 7, 8

Hi Steve:

### Lots 4 and 8:

The floor plans show 4 bedrooms with a full bath rough in on the basement level. Depending on how the basement is finished later on may require the future homeowners to upgrade their septic system (if the floor plans show more than 1 bedroom in the basement). Otherwise, the building permits for these two lots have been approved.

### Lot 1:

The BAT system is currently designed for 5 bedrooms but the floor plans show 6 bedrooms (guest retreat – room # 6). Please revise the floor plans or BAT Plan and resubmit for BP approval.

### Lot 7:

I still need to see the floor plans for this lot (Last email from you only included the cover page.).

Regards,

Hank

Hank Oswald, L.E.H.S. Howard County Health Department Bureau of Environmental Health Well & Septic Program 410.313.1786

115/15. Per T. modd, Lot 1 BAT will be revised.



## Bureau of Environmental Health

8930 Stanford Boulevard, Columbia, MD 21045 Main: 410-313-2640 | Fax: 410-313-2648 TDD 410-313-2323 | Toll Free 1-866-313-6300 www.hchealth.org

Facebook: www.facebook.com/hocohealth
Twitter: HowardCoHealthDep

Maura J. Rossman, M.D., Health Officer

# OPERATION AND MAINTENANCE AGREEMENT FOR AN ON-SITE SEWAGE DISPOSAL SYSTEM HAVING AN ADVANCED PRE-TREATMENT SYSTEM

E. This agreement shall run with the land and upon Owner's taking title to the Lot shall bind the Owner, their heirs, successors, and assigns to the provisions of the agreement as long as the property is in existence and after installation of the system. Owner further agrees that they shall inform in writing any subsequent purchaser or lessee of the Lot that the system shall require

maintenance or other attention. Upon taking title to the Lot, the Owner agrees to cause this agreement to be recorded in the Land Records of Howard County and assure that it becomes part of the Deed for the subject property in order that prospective buyers may be aware of the special conditions affecting this property.

- F. This agreement shall not be construed to limit any authority of the County to protect the public health, safety or comfort or to issue any other orders to take any other action which is now or may hereafter be within its authority.
- G. This agreement may be voided at any time at the discretion of the County.
- H. This agreement contains the entire agreement and understanding between the County and the Owner. There are no additional terms other than as contained in this agreement. This agreement may not be modified, except in writing signed by each of the parties or by their authorized representatives.
- I. The laws of the State of Maryland govern the provisions of all transactions pursuant to this agreement.
- J. Owner acknowledges and agrees that interior renovations to increase the number of bedrooms or an increase in living space shall not be permitted without approval from the County.

IN WITNESS WHEREOF, the parties have signed and sealed this agreement on the date indicated above.

Bed Nijon 4/15/2015		
Howard County Health Department		
July 18		
Owner #1 Signature Date	Owner#2 Signature	Date
Owner #1 Print Name	Owner #2 Print Name	
Minary 1 4-15-15		
Buyer #1 Signature Date  Melika Anaceson	Buyer #2 Signature	Date
Buver #1 Print Name	Buver #2 Print Name	

# 14905 VICTORY LAND

Clerk of the Circuit Court for Howard County Land Records/Licensing

The Thomas Dorsey Building 9250 Bendix Road Columbia, MD 21045 410-313-5850

LR - Agreement Recording Fee
1x 20.00 20.00

Grantor/Grantee Name: anderson
Reference/Control #: 155


LR - Agreement Surcharge
1x 40.00 40.00

SubTotal: 60.00
Total: 60.00

REV-Check-BOA 60.00 Number: 68918

04/15/2015 13:28 CC13-TR #4107182 /396/109

Thank you for visiting us today~



# GENERAL NOTES (ADDITIONAL):

REVISED PLAN SHOWN HEREON IS TO CHANGE THE SEPTIC TANK THAT IS BEING INSTALLED ONLY. ALL CALCULATIONS ARE TO REMAIN THE SAME. THIS PLAN WAS APPROVED PREVIOUSLY WITH THE ECOPOD SYSTEM. BUT DUE TO THE MEMORANDUM FROM THE HOWARD COUNTY HEALTH DEPARTMENT DATED FEBRUARY 2015: THOSE SYSTEMS ARE NO LONGER TO BE USED IF NOT INSTALLED BY MARCH 15, 2015.

> Approved Septic System Plan Howard County Health Department Hank Osund 3/25/15



### PROPOSED GROUND ELEVATION 516.0'+ AT OUTSIDE FACE OF BASEMENT FOUNDATION WALL = 516.0' 515.0' PROPOSED GROUND ELEVATION ABOVE **ELEVATION** CLEANOUT/BEND 514.0' PROPOSED SEPTIC TANK = 510.8' = 511.85(ELEV = 508.3')513.0' CLEANOUT/BEND PROPOSED GROUND ELEVATION ABOVE PROPOSED DISTRIBUTION (ELEV = 507.8')CLEANOUT/BEND BOX = 509.5'511.0' (ELEV = 508.9')INV. IN 510 0 TOP OF SEPTIC 509.0 = 507.1' CLEANOUT/BEND INV. OUT TANK = 507.8'S 508.0'-(ELEV = 506.5')= 506.8INV. OUT AT ₹ 507.0' BUILDING = 510.1' INV. IN = 506.5SEPTIC TANK SEPTIC SYSTEM DETAIL (1,300 GAL.) TO DRAINAGE FIELD 12.17' LENGTH (NOT TO SCALE) INV. OUT = 506.2'6.00' WDTH 5.00' HIGH DEPTH OF SEPTIC TANK AND DISTRIBUTION BOX ARE 506.0' SHOWN FOR GRAPHIC PURPOSES ONLY; INVERTS AND TOP DISTRIBUTION BOX ELEVATION OF SEPTIC TANK ARE ACCURATE. 1.17' LENGTH 2.33' WIDTH 0.83' HIGH (DISTANCE FROM OUTSIDE FACE OF FOUNDATION WALL)

SEPTIC SYSTEM/BEST AVAILABLE TECHNOLOGY (BAT) NOTES:


- 1. ANY CHANGE TO THE LOCATIONS OR DEPTHS TO ANY COMPONENTS MUST BE APPROVED BY THE ENGINEER AND THE HOWARD COUNTY HEALTH DEPARTMENT PRIOR TO INSTALLATION. A REVISED SITE
- 2. THE MAXIMUM DEPTH OF THE BAT PER THE MANUFACTURER'S SPECIFICATION IS 3 FEET COVER.
- THE BLOWER MAY NOT BE LOCATED MORE THAN 100 FEET FROM THE TANK BASED ON THE MANUFACTURER'S SPECIFICATIONS.
- 4. THE BAT SYSTEM SHALL BE MAINTAINED AND OPERATED FOR THE LIFE OF THE SYSTEM.
- 5. THE BAT SHALL BE OPERATED BY AND MAINTAINED BY A CERTIFIED SERVICE PROVIDER.


PROFESSIONAL ENGINEER

- . WITHIN ONE MONTH OF INSTALLATION, A PERSON INSTALLING THE BAT SYSTEM SHALL REPORT TO THE MARYLAND DEPARTMENT OF THE ENVIRONMENT (MDE), IN A MANNER ACCEPTABLE TO MDE, THE ADDRESS 4. TRENCH DESIGN, FIRST REPLACEMENT: AND DATE OF COMPLETION OF THE BAT INSTALLATION AND THE TYPE OF BAT INSTALLED.
- ELECTRICAL WORK FOR THE BAT INSTALLATION MUST BE PERFORMED BY A LICENSED ELECTRICIAN.
- B. AN AGREEMENT AND EASEMENT MUST BE COMPLETED AND SIGNED BY ALL APPLICABLE PARTIES, AND RECORDED IN THE LAND RECORDS OF HOWARD COUNTY.
- 9. THE HEALTH DEPARTMENT REQUIRES DOCUMENTATION FOR THE START-UP CERTIFICATION FROM THE MANUFACTURER PRIOR TO FINAL APPROVAL OF THE INSTALLATION.

APPROVED: FOR HOWARD COUNTY DEPARTMENT OF PLANNING & ZONING

CHIEF, DEVELOPMENT ENGINEERING DIVISION DATE DATE DIRECTOR





PROPOSED INVERT AT FOUNDATION WALL: 509.8' 1. EX. GRADE OVER TANK: 510.0' PROPOSED GRADE OVER TANK: 510.8'

2. DISTRIBUTION BOX: EXISTING GRADE OVER BOX: 509.5' PROPOSED GRADE OVER BOX: 509.5' INVERT IN: 506.5' INVERT OUT: 506.2'

3. TRENCH DESIGN:

DATE

 $(5 BDRM \times 150 GPD/BDRM = 750 GPD)$ 750 GPD + 0.6 APP. RATE = 1,250 SF USE 3' WIDE TRENCH WITH 42" GRAVEL BELOW PIPE 10' MIN. SPACING BETWEEN TRENCH EDGES 1,250 SF ÷ 3' WIDTH = 416.67 LF x 0.71 = 295.84 LF MIN. TRENCH USE 4 74' LONG TRENCHES = 296 LF

 $(5 BDRM \times 150 GPD/BDRM = 750 GPD)$ 750 GPD ÷ 0.6 APP. RATE = 1,250 SF USE 3' WIDE TRENCH WITH 60" GRAVEL BELOW PIPE 10' MIN. SPACING BETWEEN TRENCH EDGES 1,250 SF ÷ 3' WIDTH = 416.67 LF x 0.83 = 345.84 LF MIN. TRENCH USE 5 70' LONG TRENCHES = 350 LF

SITE PLAN FOR BAT INSTALLATION

LOT 1

MERIWETHER FARMS

LIBER 13779, FOLIO 473

PLAT No. 21751

TAX No. 04-593610 FOURTH ELECTION DISTRICT

HOWARD COUNTY, MARYLAND

ADDRESS: 14905 VICTORY LANE

GLENELG, MARYLAND

EFFECTIVE SIDEWALL (6') BOTTOM MAX. DEPTH (7.5') TRENCH 1 (T1): GROUND ABOVE = 509.6' INV. IN = 505.6BOTTOM TRENCH = 502.1

RENCH 2 (T2): GROUND ABOVE = 509.6' INV. IN = 505.6BOTTOM TRENCH = 502.1'

GROUND ABOVE = 508.8' INV. IN = 504.8'BOTTOM TRENCH = 501.3'

TRENCH 4 (T4):

GROUND ABOVE = 508.8' INV. IN = 504.8'BOTTOM TRENCH = 501.3'

# (FIRST REPLACEMENT) APP. RATE (0.6)

EFFECTIVE SIDEWALL (6') BOTTOM MAX. DEPTH (7') TRENCH 5 (T5): GROUND ABOVE = 507.8' INV. IN = 505.8BOTTOM TRENCH = 500.8

TRENCH 6 (T6): GROUND ABOVE = 508.0' INV. IN = 506.0BOTTOM TRENCH = 501.0'


TRENCH 7 (17): GROUND ABOVE = 506.9' INV. IN = 504.9BOTTOM TRENCH = 499.9'

TRENCH 8 (T8): GROUND ABOVE = 507.4' INV. IN = 505.4

TRENCH 9 (T9):

GROUND ABOVE = 505.9INV. IN = 503.9BOTTOM TRENCH = 498.9'

BOTTOM TRENCH = 500.4'



# VICINITY MAP

# GENERAL NOTES:

- 1. THE SUBJECT PROPERTY IS ZONED RC-DEO PER THE 2/2/04 COMPREHENSIVE ZONING PLAN AND PER COMP-LITE ZONING REGULATIONS DATED 7/28/06.
- 2. PLAT REFERENCE: PLAT No. 21751.
- 3. THE EXISTING TOPOGRAPHY WITHIN THE AREA OF PROPOSED WORK IS TAKEN FROM FIELD RUN SURVEY WITH MAXIMUM TWO FOOT CONTOUR INTERVALS PREPARED BY ESE. DATED 06/06/13.
- 4. SEE ARCHITECTURAL PLANS FOR BUILDING DIMENSIONS AND DESIGN DETAILS. PRIOR TO STAKEOUT FOR CONSTRUCTION, IT SHALL BE THE OWNER/BUILDERS RESPONSIBILITY TO PROVIDE ESE CONSULTANTS INC. WITH THE MOST RECENT SET OF HOUSE PLANS.
- 5. THE CONTRACTOR OR DEVELOPER SHALL NOTIFY THE DEPARTMENT OF PUBLIC WORKS / BUREAU OF ENGINEERING / CONSTRUCTION INSPECTION DIVISION AT (410-313-1881) AT LEAST FIVE (5) WORKING DAYS PRIOR TO THE START OF WORK.
- 6. THE CONTRACTOR SHALL NOTIFY "MISS UTILITY" AT 1-800-257-7777 AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO ANY EXCAVATION WORK BEING DONE.
- 7. TOTAL LIMIT OF DISTURBANCE: 43,441 SQ. FT. / 1.00 AC.±
- 8. STORMWATER MANAGEMENT FOR THIS LOT IS PROVIDED BY PREVIOUSLY APPROVED PLAN F-08-199
- 9. ANY DAMAGE TO PUBLIC "RIGHT-OF-WAYS" OR PAVED PUBLIC ROADS SHALL BE REPAIRED IMMEDIATELY AT THE CONTRACTORS EXPENSE IN ACCORDANCE WITH THE HOWARD COUNTY STANDARDS AND SPECIFICATIONS.
- 10. DEVIATIONS FROM THESE PLANS AND SPECIFICATIONS WITHOUT PRIOR WRITTEN CONSENT OF THE CIVIL ENGINEER (ESE) MAY CAUSE THE WORK TO BE UNACCEPTABLE.
- 11. THE DIMENSIONED DISTANCES SHALL GOVERN IF SCALED AND DIMENSIONED DISTANCES ON THIS PLAN ARE FOUND TO BE IN DISAGREEMENT.
- 12. THE LOTS SHOWN HEREON COMPLY WITH THE MINIMUM LOT AREA AND OWNERSHIP WIDTH AS REQUIRED BY THE MARYLAND DEPARTMENT OF THE ENVIRONMENT.
- 13. THESE AREAS DESIGNATE A PRIVATE SEWAGE EASEMENT OF AT LEAST 10,000 SQUARE FEET AS REQUIRED BY THE MARYLAND DEPARTMENT OF THE ENVIRONMENT FOR INDIVIDUAL SEWAGE DISPOSAL. IMPROVEMENTS OF ANY NATURE THIS AREA ARE RESTRICTED UNTIL PUBLIC SEWAGE IS AVAILABLE. THESE EASEMENTS SHALL BECOME NULL AND VOID UPON CONNECTION TO A PUBLIC SEWAGE SYSTEM. THE COUNTY HEALTH OFFICER SHALL HAVE THE AUTHORITY TO GRANT VARIANCES FOR ENCROACHMENTS UNTO THE PRIVATE SEWAGE EASEMENT. RECORDATION OF A MODIFIED SEWAGE EASEMENT SHALL NOT BE NECESSARY.
- 14. EXISTING WELLS, SEPTIC SYSTEMS, AND SEWAGE DISPOSAL AREAS WITHIN 100' OF THE PROPERTY AND THOSE WELLS WITHIN 200' DOWN GRADIENT OF EXISTING OR PROPOSED SEPTIC SYSTEMS OR SEWAGE DISPOSAL AREAS HAVE BEEN SHOWN.
- 15. ANY CHANGES TO A PRIVATE SEWAGE AREA SHALL REQUIRE A REVISED PERCULATION CERTIFICATION PLAN
- 16. UPON BUILDING PERMIT REVIEW THE SEPTIC SYSTEMS FOR ALL PROPOSED STRUCTURES AND/OR EXISTING STRUCTURE EXPANSIONS SHALL BE RE-EVALUATED TO DETERMINE SUFFICIENT SYSTEM CAPACITY.
- 17. THE DEVELOPMENT OF THIS LOT DOES NOT REQUIRE AN ENVIRONMENTAL CONCEPT PLAN SINCE STORMWATER MANAGEMENT WAS PREVIOUSLY APPROVED UNDER
- 18. A STANDARD SEDIMENT CONTROL PLAN MAY BE USED FOR DEVELOPMENT OF THIS LOT. REFERENCE GRADING PLAN DATED 12/18/13.
- 19. THE EXISTING WELL(S) SHOWN ON THIS PLAN (IDENTIFIED WITH THE ATTACHED WELL TAG NUMBER HO-95-2079 HAS BEEN FIELD LOCATED BY ESE CONSULTANTS -PROFESSIONAL LAND SURVEYOR(S), AND IS ACCURATELY SHOWN.
- 20.BUILDING SETBACKS (B.R.L's) SHOWN HEREON PER SITE DEVELOPMENT PLAN
- SETBACK DISTANCES SHOWN HEREON AS "±" HAVE AN ACCURACY OF ±0.1' FOOT. 21. CULVERT FOR DRIVEWAY IS NOT NEEDED AS SHOWN ON SHEET 7 OF 15 OF THE
- STORM DRAIN PROFILES PLAN IN A COLUMN LABELED "DRIVEWAY FOR CULVERT DATE", PER F-08-199 PLAN.



Engineering Land Surveying

ESE Consultants Inc. 7164 Columbia Gateway Dr. Suite 230 Columbia, MD 21046 TEL: 410-872-9105 FAX: 410-872-4870

DATE: 03/15/15 CHK'D: M.J.B

SCALE: 1"=40 FILE: BAT LOT 1\_revi JOB NO: 3184 DRAWN: R.C.K