

RECEIVED

PERMIT NUMBER: B 20002731

DATE ACCEPTED:

AUG 12 2020

RESIDENTIAL BUILDING PERMIT APPLICATION						LICENSES & PERMITS DIVISION	
HOWARD COUNTY DEPARTMENT OF INSPECTIONS, LICENSES, AND PERMITS 3430 COURT HOUSE DRIVE, ELLICOTT CITY, MD 21043 - PHONE: (410) 313-2455 OPTION #4 www.howardcountymd.gov							
BUILDING SITE ADDRESS REQUIRED							
Street Address: 1019 Fairlane Road					Unit:		
City: Woodbine			State: MD		Zip Code: 21797		
Subdivision/Village/Complex Name: Fairlane Farm #41					SDP/WP/BA #:		
Lot: 17		Tax Map: 0008		Parcel: 0008		Grading Permit #:	
DESCRIPTION OF WORK REQUIRED							
Existing Use:			Proposed Use:			Estimated Cost: \$ 25000	
Trade Work to Be Completed (Separate Permits Required): <input type="checkbox"/> Mechanical (HVACR) <input type="checkbox"/> Electrical <input type="checkbox"/> Plumbing <input type="checkbox"/> None							
INST 600 # CONC Pool 18X34							
Depth - to - ft.							
PROPERTY OWNER INFORMATION REQUIRED							
Owner(s) Name(s) (As it appears on tax records): Gerald Kriskovich					Primary Residence: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
Owner's Street Address: 1019 Fairlane Road							
City: Woodbine			State: MD		Zip Code: 21797		
Phone: 406-214-6961			Email: KRISOVICH, JERRY @ Gmail.com				
APPLICANT NAME REQUIRED - INDIVIDUAL WHO SIGNS THIS APPLICATION							
Business Name: NOVA Builders Inc					Contact Name: Mark Deeks		
Street Address: 7462 Railroad Ave #100							
City: Hampden			State: MD		Zip Code: 21077		
Phone: 410-766-1770			Email: NOVA9 @ Comcast.net				
CONTRACTOR INFORMATION REQUIRED							
Business Name: NOVA Builders Inc							
Licensee's Name: MARK DEEKS/ACT Take					License #: 45377		
Street Address: 7462 Railroad Ave #100							
City: Hampden			State: MD		Zip Code: 21077		
Phone: 410-766-1770			Email: NOVA9 @ Comcast.net				
ARCHITECT/ENGINEER INFORMATION INDIVIDUAL WHO SIGNED PLANS, IF APPLICABLE							
Business Name:					Name:		
Street Address:							
City:			State:		Zip Code:		
Phone:			Email:				
BUILDING CHARACTERISTICS REQUIRED							
Primary Structure: <input checked="" type="checkbox"/> SF Dwelling <input type="checkbox"/> SF Townhouse <input type="checkbox"/> SF Duplex <input type="checkbox"/> Mobile Home <input type="checkbox"/> Multi-Family Dwelling (MF*)					Condo: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
Utilities: <input type="checkbox"/> Electric <input type="checkbox"/> Gas		Water Supply: <input type="checkbox"/> Public <input checked="" type="checkbox"/> Private (Well)		Sewage Disposal: <input type="checkbox"/> Public <input checked="" type="checkbox"/> Private (Septic)			
Heating System: <input type="checkbox"/> Electric <input type="checkbox"/> Natural Gas <input type="checkbox"/> Propane <input type="checkbox"/> Other:					Roadside Tree Project: <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes: #		
Sprinkler System: <input type="checkbox"/> NFPA 13 <input type="checkbox"/> NFPA 13R <input type="checkbox"/> NFPA 13D <input type="checkbox"/> None					Fire Alarm System: <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Voice Evac		
ADDITIONAL RESIDENTIAL INFORMATION (PLEASE SELECT/COMPLETE ALL THAT APPLY)							
Model Name & Options:							
# of Bedrooms (SF):		# of efficiency units (MF*):		# of 1 BR (MF*):		# of 2 BR (MF*):	
# of 3 BR (MF*):		# Rooms:		# Full Baths:		# Half Baths:	
# Fireplaces:		Garage/Carport Info: <input type="checkbox"/> Attached Garage <input type="checkbox"/> Detached Garage <input type="checkbox"/> Integral Garage <input type="checkbox"/> Carport <input type="checkbox"/> None					
Basement/Foundation Info: <input type="checkbox"/> Slab on Grade <input type="checkbox"/> Post & Pier <input type="checkbox"/> Unfinished Basement <input type="checkbox"/> Finished Basement: <input type="checkbox"/> Full or <input type="checkbox"/> Partial							
1st Fl Width:		1st Fl Depth:		2nd Fl Width:		2nd Fl Depth:	
Bsmt Width:		Bsmt Depth:		Energy Method: <input type="checkbox"/> Prescriptive <input type="checkbox"/> Performance <input type="checkbox"/> UA Alternative <input type="checkbox"/> ERI			
Gross Area: sq ft				Occupiable Area: sq ft			
AGREEMENT/ DISCALIMER REQUIRED							
THE UNDERSIGNED HEREBY CERTIFIES AND AGREES AS FOLLOWS: (1) THAT HE/SHE IS AUTHORIZED TO MAKE THIS APPLICATION; (2) THAT THE INFORMATION IS CORRECT; (3) THAT HE/SHE WILL COMPLY WITH ALL REGULATIONS OF HOWARD COUNTY WHICH ARE APPLICABLE THERETO; (4) THAT HE/SHE WILL PERFORM NO WORK ON THE ABOVE REFERENCED PROPERTY NOT SPECIFICALLY DESCRIBED IN THIS APPLICATION; (5) THAT HE/SHE GRANTS COUNTY OFFICIALS THE RIGHT TO ENTER ONTO THIS PROPERTY FOR THE PURPOSE OF INSPECTING THE WORK PERMITTED AND POSTING NOTICES.							
APPLICANT'S ORIGINAL SIGNATURE: MS					DATE SIGNED: 7-31-2020		
FOR OFFICE USE ONLY							
CHECKS PAYABLE TO: DIRECTOR OF FINANCE OF HOWARD COUNTY							
AGENCIES REQUIRED/APPROVALS:							
<input checked="" type="checkbox"/> PR		<input checked="" type="checkbox"/> DPZ		<input checked="" type="checkbox"/> DED		<input checked="" type="checkbox"/> Health 9.29.20	
<input type="checkbox"/> SHA		<input type="checkbox"/> CID					
SUBMITTAL FEES: \$275.00		PAYMENT: *NONE SUBMITTED		ACCEPTED BY: DROPBOX			

Oswald, Hank

From: NOVA POOL AND SPA SERVICE AND SPA SERVICE <nova9@comcast.net>
Sent: Thursday, September 10, 2020 9:28 AM
To: Oswald, Hank
Subject: Fwd: Kriskovich signed letter for B20002731
Attachments: ATT00001.htm; kriskovich letter to county setback.pdf

[Note: This email originated from outside of the organization. Please only click on links or attachments if you know the sender.]

Morning Hank

Here is the signed letter from homeowner for the waiver on permit above

Thanks

Zena

Please confirm received


----- Original Message -----

From: Jerry Kriskovich <kriskovich.jerry@gmail.com>
To: NOVA POOL AND SPA SERVICE AND SPA SERVICE <nova9@comcast.net>, Jerry Kriskovich <kriskovich.jerry@gmail.com>
Date: 09/10/2020 9:23 AM
Subject: Fwd: Kriskovich signed letter

Here you go. Thanks

----- Forwarded message -----

From: **Jerry Kriskovich** <jkriskovich@opcmiajobcorps.org>
Date: Thu, Sep 10, 2020 at 9:21 AM
Subject: Kriskovich signed letter
To: kriskovich Jerry <kriskovich.jerry@gmail.com>



Bureau of Environmental Health

8930 Stanford Boulevard, Columbia, MD 21045

Main: 410-313-2640 | Fax: 410-313-2648

TDD 410-313-2323 | Toll Free 1-866-313-6300

www.hchealth.org

Facebook: www.facebook.com/hocohealth

Twitter: HowardCoHealthDep

Maura J. Rossman, M.D., Health Officer

September 24, 2020

Jerry Kriskovich
1019 Fairlane Road
Woodbine, MD 21797

RE: Waiver Approval
1019 Fairlane Road
Woodbine, MD 21797

Mr. Kriskovich,

This letter is being issued in response to your waiver request dated September 10, 2020. Your request for a waiver of the Howard County Code twenty (20) setback for a pool to the existing on-site sewage disposal system trench has been **approved**. The proposed thirty-four (34) by eighteen (18) foot pool has been approved ten (10) feet from the existing on-site sewage disposal system trench. Additionally, the pool safety fencing as illustrated on the site plan may be installed in the sewage disposal area.

Be advised that a condition of this waiver requires temporary fencing to be installed five (5) feet from the tank and trenches extending across the entire property to prevent any vehicle or construction equipment traffic in that area during the construction of the pool. The temporary fencing must be installed prior to building permit approval.

Any deviations from the proposed work illustrated on the site plan submitted with the waiver request will be subject to further review by this department.

Any questions regarding this decision may be directed to the Well and Septic Program of the Howard County Health Department.

Respectfully,

Michael J. Davis
Assistant Director
Bureau of Environmental Health


September 10, 2020

Attention: Howard County Permits
Deputy Director Mike Davis

Re: B20002731
1019 Fairlane Road
Woodbine Md 21797

Deputy Director Mike Davis,

I Mr. Kriskovich writing this letter to ask for a waiver to reduce the setback distance between the pool and the sewage disposal area from 20 feet to 10 feet, I would also like to put a portion of the safety fence within the sewage disposal area as well, Thank You in advance for your assistance in this matter

Sincerely,

Jerry Kriskovich

Oswald, Hank

From: Williams, Jeffrey
Sent: Tuesday, September 1, 2020 9:45 AM
To: Oswald, Hank
Subject: RE: Quick Question

We have some leeway there and 2' isn't that tall, but we should see how close at its closest point and get any info on drainage pipes. I'd look for at least 5' if no drainage pipe assuming the wall is higher than the SDA. It shouldn't be too close to the tank either. We'd have to ask about the size of the gravel base and how close that would be to the tank. Look slike the pool may be closer than 20' to the SDA? I'd also look at that fence location vs existing trenches and perc results. If we need shallow zone for trenches (unlikely) we'd have to take a closer look at the fence. They'll need to give us the depth of the fence post holes and we can compare that to the trench depths. They will need to do a waiver request.

From: Oswald, Hank <hoswald@howardcountymd.gov>
Sent: Tuesday, September 1, 2020 9:09 AM
To: Williams, Jeffrey <jewilliams@howardcountymd.gov>
Subject: Quick Question

Hi Jeff- Should I treat the 24 inch high walls on this site plan as steep slopes with a 25 foot setback?

Sent from my Verizon, Samsung Galaxy smartphone
Get [Outlook for Android](#)

Oswald, Hank

From: Oswald, Hank
Sent: Friday, September 4, 2020 4:05 PM
To: NOVA9@COMCAST.NET
Subject: Re: B20002731_1019 Fairlane Road

Hi Zena:

Okay. When the owner writes the waiver request to reduce the setback distance between the pool and the sewage disposal area from 20 feet to _____, please also add in that you would like to also install a portion of the safety fence within the sewage disposal area as well.

Let me know if you have any questions about this.

Thanks,

Hank

Hank Oswald
Howard County Health Department
Well and Septic Program

From: NOVA9@COMCAST.NET <NOVA9@COMCAST.NET>
Sent: Friday, September 4, 2020 2:39 PM
To: Oswald, Hank <hoswald@howardcountymd.gov>
Subject: Re: B20002731_1019 Fairlane Road

[Note: This email originated from outside of the organization. Please only click on links or attachments if you know the sender.]

Hank
Mark said 10ft
Zena

On 09/04/2020 2:32 PM Oswald, Hank <hoswald@howardcountymd.gov> wrote:

Based on the site plan, one wall appears much closer to the septic tank? Can you confirm that distance for me?

From: NOVA9@COMCAST.NET <NOVA9@COMCAST.NET>
Sent: Friday, September 4, 2020 2:30 PM
To: Oswald, Hank <hoswald@howardcountymd.gov>
Subject: Re: B20002731_1019 Fairlane Road

[Note: This email originated from outside of the organization. Please only click on links or attachments if you know the sender.]

Hank
The closet wall to the septic is 10ft
Mark

On 09/04/2020 2:25 PM Oswald, Hank <hoswald@howardcountymd.gov> wrote:

Hello Mark:

Can you provide an answer to the distances that I asked about in #1, so I consult with me supervisor on this BP.

Thanks,

Hank

Hank Oswald
Howard County Health Department
Well and Septic Program

From: NOVA9@COMCAST.NET <NOVA9@COMCAST.NET>
Sent: Thursday, September 3, 2020 2:00 PM
To: Oswald, Hank <hoswald@howardcountymd.gov>
Subject: RE: B20002731_1019 Fairlane Road

[Note: This email originated from outside of the organization. Please only click on links or attachments if you know the sender.]

On 09/03/2020 10:27 AM Oswald, Hank
<hoswald@howardcountymd.gov> wrote:

Question 1 - I need to know the distance from the walls closest point to the existing septic tank and sewage disposal area (SDA). 10FT

From: NOVA9@COMCAST.NET <NOVA9@COMCAST.NET>
Sent: Thursday, September 3, 2020 10:17 AM
To: Oswald, Hank <hoswald@howardcountymd.gov>
Subject: Re: B20002731_1019 Fairlane Road

[Note: This email originated from outside of the organization. Please only click on links or attachments if you know the sender.]

Morning Hank
Please see answers below we are working on the letter
Zena/Mark

On 09/03/2020 9:04 AM Oswald, Hank
<hoswald@howardcountymd.gov> wrote:

Hello Mr. Weeks:

I have couple of questions regarding the site plan for building permit # B20002731 (1019 Fairlane Road).

- 1.) What is the 24 inch wall closest point to the septic tank & sewage disposal area (SDA)? Made of shotcrete with verneer and coping
- 2.) Does the wall have drainage pipes? Yes 4" drain tile
- 3.) What is the size of the walls gravel base? 12"x 12"
- 4.) The required setback distance from a pool to the SDA is 20 feet. Anything closer will require a written waiver request by the homeowner to reduce the setback (from 20 ft. to ____). Please address the letter to Deputy Director, Mike Davis.
- 5.) What is the depth of the fence post inside the SDA? 24inch

Should you have any questions, please don't hesitate to ask.

Thanks,

Hank

Hank Oswald, LEHS
Howard County Health Department
Well and Septic Program
410.313.1786

Oswald, Hank

From: NOVA9@COMCAST.NET
Sent: Friday, September 4, 2020 2:39 PM
To: Oswald, Hank
Subject: Re: B20002731_1019 Fairlane Road

[Note: This email originated from outside of the organization. Please only click on links or attachments if you know the sender.]

Hank
Mark said 10ft
Zena

On 09/04/2020 2:32 PM Oswald, Hank <hoswald@howardcountymd.gov> wrote:

Based on the site plan, one wall appears much closer to the septic tank? Can you confirm that distance for me?

From: NOVA9@COMCAST.NET <NOVA9@COMCAST.NET>
Sent: Friday, September 4, 2020 2:30 PM
To: Oswald, Hank <hoswald@howardcountymd.gov>
Subject: Re: B20002731_1019 Fairlane Road

[Note: This email originated from outside of the organization. Please only click on links or attachments if you know the sender.]

Hank
The closet wall to the septic is 10ft
Mark

On 09/04/2020 2:25 PM Oswald, Hank <hoswald@howardcountymd.gov> wrote:

Hello Mark:

Can you provide an answer to the distances that I asked about in #1, so I consult with me supervisor on this BP.

Thanks,

Hank

Hank Oswald
Howard County Health Department
Well and Septic Program

From: NOVA9@COMCAST.NET <NOVA9@COMCAST.NET>
Sent: Thursday, September 3, 2020 2:00 PM
To: Oswald, Hank <hoswald@howardcountymd.gov>
Subject: RE: B20002731_1019 Fairlane Road

[Note: This email originated from outside of the organization. Please only click on links or attachments if you know the sender.]

On 09/03/2020 10:27 AM Oswald, Hank
<hoswald@howardcountymd.gov> wrote:

Question 1 - I need to know the distance from the walls closest point to the existing septic tank and sewage disposal area (SDA). 10FT

From: NOVA9@COMCAST.NET <NOVA9@COMCAST.NET>
Sent: Thursday, September 3, 2020 10:17 AM
To: Oswald, Hank <hoswald@howardcountymd.gov>
Subject: Re: B20002731_1019 Fairlane Road

[Note: This email originated from outside of the organization. Please only click on links or attachments if you know the sender.]

Morning Hank

Please see answers below we are working on the letter

Zena/Mark

On 09/03/2020 9:04 AM Oswald, Hank
<hoswald@howardcountymd.gov> wrote:

Hello Mr. Weeks:

I have couple of questions regarding the site plan for building permit # B20002731 (1019 Fairlane Road).

- 1.) What is the 24 inch wall closest point to the septic tank & sewage disposal area (SDA)? Made of shotcrete with verneer and coping
- 2.) Does the wall have drainage pipes? Yes 4" drain tile
- 3.) What is the size of the walls gravel base? 12"x 12"
- 4.) The required setback distance from a pool to the SDA is 20 feet. Anything closer will require a written waiver request by the homeowner to reduce the setback (from 20 ft. to ____). Please address the letter to Deputy Director, Mike Davis.
- 5.) What is the depth of the fence post inside the SDA? 24inch

Should you have any questions, please don't hesitate to ask.

Thanks,

Hank

Hank Oswald, LEHS

Howard County Health Department

Well and Septic Program

410.313.1786

Oswald, Hank

From: Williams, Jeffrey
Sent: Friday, September 4, 2020 3:34 PM
To: Oswald, Hank
Subject: Re: Quick Question_1019 Fairlane Road_ Wall and In-ground Pool

Have them add the fence into the waiver. I'd call the wall ok unless the drain tile is aiming right at the tank

Get [Outlook for Android](#)

From: Oswald, Hank <hoswald@howardcountymd.gov>
Sent: Friday, September 4, 2020 3:18:00 PM
To: Williams, Jeffrey <jewilliams@howardcountymd.gov>
Subject: Re: Quick Question_1019 Fairlane Road_ Wall and In-ground Pool

Jeff:

The contractor said the wall is 10 feet from the septic tank. It's made of shotcrete with verneer and coping. The was has 4 inch drain tile. The walls gravel base is 12" x 12". The depth of the fence post is 24 inches. The septic record indicates the trench inlet to be at 3 feet. I believe they are going to submit a waiver letter reduce the pool distance to the SDA.

Hank

From: Williams, Jeffrey <jewilliams@howardcountymd.gov>
Sent: Tuesday, September 1, 2020 9:44 AM
To: Oswald, Hank <hoswald@howardcountymd.gov>
Subject: RE: Quick Question

We have some leeway there and 2' isn't that tall, but we should see how close at its closest point and get any info on drainage pipes. I'd look for at least 5' if no drainage pipe assuming the wall is higher than the SDA. It shouldn't be too close to the tank either. We'd have to ask about the size of the gravel base and how close that would be to the tank. Look slike the pool may be closer than 20' to the SDA? I'd also look at that fence location vs existing trenches and perc results. If we need shallow zone for trenches (unlikely) we'd have to take a closer look at the fence. They'll need to give us the depth of the fence post holes and we can compare that to the trench depths. They will need to do a waiver request.

From: Oswald, Hank <hoswald@howardcountymd.gov>
Sent: Tuesday, September 1, 2020 9:09 AM
To: Williams, Jeffrey <jewilliams@howardcountymd.gov>
Subject: Quick Question

Hi Jeff- Should I treat the 24 inch high walls on this site plan as steep slopes with a 25 foot setback?

Sent from my Verizon, Samsung Galaxy smartphone
Get [Outlook for Android](#)

- 1) THIS LOCATION DRAWING IS PREPARED FOR THE BENEFIT OF THE CLIENT SIGNING THE HOUSE LOCATION SURVEY APPROVAL FORM INsofar AS IT IS REQUIRED BY A LENDER OR TITLE INSURANCE COMPANY OR ITS AGENTS IN CONNECTION WITH THE CONTEMPLATED TRANSFER, FINANCING OR REFINANCING OF THE PROPERTY SHOWN HEREON. UNLESS INDICATED AS BEING A BOUNDARY SURVEY, THIS LOCATION DRAWING IS NOT INTENDED FOR USE IN THE ESTABLISHMENT OF PROPERTY LINES AND IS NOT TO BE RELIED UPON FOR THE ESTABLISHMENT OR LOCATIONS OF FENCES, GARAGES, BUILDINGS OR OTHER EXISTING OR FUTURE IMPROVEMENTS. AS A RESULT, THIS LOCATION DRAWING DOES NOT PROVIDE FOR ACCURATE IDENTIFICATION OF PROPERTY LINES, BUT SUCH IDENTIFICATION MAY NOT BE REQUIRED FOR THE TRANSFER OF TITLE OR SECURING FINANCING FOR RE-FINANCING.
- 2) SUBJECT PROPERTY IS SHOWN IN ZONE X ON THE NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP OF HOWARD COUNTY, MARYLAND, COMMUNITY PANEL No. 24027000350, EFFECTIVE 11-01-2013.
- 3) THE OFFSETS FROM BUILDING LINE TO PROPERTY LINE AS SHOWN ON THE PLAT HEREON ARE TO AN ACCURACY OF PLUS OR MINUS 0.5'.
- 4) NO TITLE REPORT FURNISHED. SUBJECT TO ALL EASEMENTS, RIGHTS OF WAY AND CONDITIONS OF RECORD.
- 5) THE EXISTING WELL(S) SHOWN ON THIS PLAN (IDENTIFIED WITH THE ATTACHED WELL TAG NUMBER HO-15-0352 HAS BEEN FIELD LOCATED BY FISHER, COLLINS AND CARTER, INC. PROFESSIONAL LAND SURVEYORS AND IS ACCURATELY SHOWN.
- 6) PROFESSIONAL CERTIFICATION: I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED BY ME OR UNDER MY RESPONSIBLE CHARGE, AND THAT I AM A DULY LICENSED PROPERTY LINE SURVEYOR UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 339, EXPIRATION DATE 10/04/2018.
- 7) BUILDING PERMIT #0-18000987

Legend

- Private Drainage & Utility Easement
- 10' Public Tree Maintenance Easement
- 36' Private Access And Stormwater Management Easement For Lots 15 Thru 18
- Private Use-In-Common Access Easement

Public And Private Drainage & Utility Easement Line Table

LINE	BEARING	LENGTH
D22	S85°37'32"E	106.11'
D23	N59°10'37"E	231.25'
D24	S30°49'23"E	20.00'
D25	S59°10'37"W	237.59'
D26	N03°37'32"W	112.08'
D27	N03°18'26"E	20.00'

24' Private Use-In-Common Access Easement Line Table

LINE	BEARING	LENGTH
UIC-1	N03°18'26"E	234.62'
UIC-2	N28°30'06"W	186.50'
UIC-3	N61°29'54"E	24.00'
UIC-4	S28°30'06"E	193.34'
UIC-5	S03°18'26"W	237.32'

36' Private Access And Stormwater Management Easement Line Table

LINE	BEARING	LENGTH
SWM-1	N03°18'26"E	234.90'
SWM-2	N28°30'06"W	183.08'
SWM-3	N61°29'54"E	36.00'
SWM-4	S28°30'06"E	193.34'
SWM-5	S03°18'26"W	237.32'

#1019 FAIRLANE ROAD
B.R.L. = BUILDING RESTRICTION LINE
TOP OF FOUNDATION ELEVATION = 603.1'±




Mark L. Robert 6/11/18
PROPERTY LINE SURVEYOR
REG. #339

HOUSE LOCATION DRAWING

FOUNDATION LOCATION: 5/31/18
FINAL LOCATION:
BOUNDARY SURVEY:

SCALE: 1"=20'
DATE: 6/11/18
DRAWN BY: MD
CHECKED BY: MLE
PROJECT No. 25105-3003



Part Of
Buildable
Preservation
Parcel 'A'

Wall Chuck
OK House has
moved slightly
7-5-18

DETAIL:
1"=20'

LOT 17
FAIRLANE FARM
PHASE ONE
LOTS 1 THRU 18, BUILDABLE PRESERVATION PARCEL
'A', NON-BUILDABLE PRESERVATION PARCELS 'B' THRU
'E', PARCEL 'F', NON-BUILDABLE BULK PARCELS 'G'
AND 'H' AND FOREST MITIGATION BANK
PLAT NOS. 24251 THRU 24259
FOURTH ELECTION DISTRICT
HOWARD COUNTY, MARYLAND

Oswald, Hank

From: Oswald, Hank
Sent: Friday, September 4, 2020 3:18 PM
To: Williams, Jeffrey
Subject: Re: Quick Question_1019 Fairlane Road_ Wall and In-ground Pool

Jeff:

The contractor said the wall is 10 feet from the septic tank. It's made of shotcrete with verneer and coping. The was has 4 inch drain tile. The walls gravel base is 12" x 12". The depth of the fence post is 24 inches. The septic record indicates the trench inlet to be at 3 feet. I believe they are going to submit a waiver letter reduce the pool distance to the SDA.

Hank


From: Williams, Jeffrey <jewilliams@howardcountymd.gov>
Sent: Tuesday, September 1, 2020 9:44 AM
To: Oswald, Hank <hoswald@howardcountymd.gov>
Subject: RE: Quick Question

We have some leeway there and 2' isn't that tall, but we should see how close at its closest point and get any info on drainage pipes. I'd look for at least 5' if no drainage pipe assuming the wall is higher than the SDA. It shouldn't be too close to the tank either. We'd have to ask about the size of the gravel base and how close that would be to the tank. Look slike the pool may be closer than 20' to the SDA? I'd also look at that fence location vs existing trenches and perc results. If we need shallow zone for trenches (unlikely) we'd have to take a closer look at the fence. They'll need to give us the depth of the fence post holes and we can compare that to the trench depths. They will need to do a waiver request.

From: Oswald, Hank <hoswald@howardcountymd.gov>
Sent: Tuesday, September 1, 2020 9:09 AM
To: Williams, Jeffrey <jewilliams@howardcountymd.gov>
Subject: Quick Question

Hi Jeff- Should I treat the 24 inch high walls on this site plan as steep slopes with a 25 foot setback?

Sent from my Verizon, Samsung Galaxy smartphone
Get [Outlook for Android](#)



Bureau of Environmental Health
8930 Stanford Boulevard, Columbia, MD 21045
Main: 410-313-2640 | Fax: 410-313-2648
TDD 410-313-2323 | Toll Free 1-866-313-6300
www.hchealth.org
Facebook: www.facebook.com/hocohealth

Maura J. Rossman, M.D., Health Officer

RECEIPT DATE: 7/5/18

ONSITE SEWAGE DISPOSAL SYSTEM

P 503048

APPROVAL DATE: 8/13/18 SEC

PERMIT: CONSTRUCTION

A

PROPERTY ADDRESS: 1019 Fairlane Road

SUBDIVISION: Fairlane Farms

LOT: 17

TAX ID: _____

CONTRACTOR: South Carroll Backhoe

EMAIL: scbackhoe@comcast.com

CONTRACTOR ADDRESS: 4410 Salem Bottom Road, Westminster, MD 21157

PHONE: 410-596-3618

PROPERTY OWNER: NV Homes

EMAIL: _____

OWNER ADDRESS: 9720 Patuxent Woods Drive, Columbia, MD 21046

PHONE: 410-379-5956

SEPTIC TANK SIZE (GALLONS): 2000

TANK MANUFACTURER: Babylon Vault or equivalent

PUMP MODEL: N/A

PUMP SIZE

N/A

PUMP TANK CAPACITY: N/A

DISTRIBUTION SYSTEM: ☒ GRAVITY

☐ PRESSURE DOSED

BEDROOMS: 5

APPLICATION RATE 1.2

TRENCHES:	LINEAR FEET REQUIRED: <u>104.6</u>	INLET DEPTH: <u>3</u>
	TRENCH WIDTH: <u>3</u>	MAXIMUM BOTTOM DEPTH: <u>6</u>
	MINIMUM SPACE BETWEEN TRENCHES: <u>10</u>	EFFECTIVE AREA BEGINNING DEPTH: <u>3</u>
LOCATION:	PER APPROVED SITE PLAN. SEWAGE DISPOSAL AREA AND TANK LOCATIONS MUST BE STAKED BY LICENSED SURVEYOR PRIOR TO PRE-CONSTRUCTION INSPECTION.	
NOTES:	Use 2 trenches @ 52.08 LF	

ISSUED BY: Hank Oswald

ISSUE DATE: 7/5/18

EXPIRATION DATE: 7/5/19

NOTE: CONTRACTOR MUST SCHEDULE A PRE-CONSTRUCTION INSPECTION PRIOR TO BEGINNING ANY INSTALLATION

NOTE: CONTRACTOR MUST SCHEDULE AN INSPECTION AND GAIN APPROVAL OF ALL COMPONENTS PRIOR TO COVERING

NOTE: STONE MUST BE APPROVED BY HEALTH DEPARTMENT AND GRAVEL TICKET MUST BE AVAILABLE FOR REVIEW.

NOTE: WATERTIGHT TANKS REQUIRED

NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE AT LEAST 100 FEET DOWNGRADIENT FROM ANY WATER WELL

NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS

NOTE: AN ELECTRICAL PERMIT IS REQUIRED FOR INSTALLATION OF ANY ELECTRICAL COMPONENTS OF THE SYSTEM

☒ ELECTRICAL PERMIT ISSUED


E _____

NOTE: MDE RECOMMENDS SEPTIC TANKS, BAT, AND OTHER PRETREATMENT UNITS BE PUMPED AT A FREQUENCY ADEQUATE TO ENSURE THAT SOLIDS ARE NOT DISCHARGED TO THE DISPOSAL AREA

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT.

CALL 410-313-1771 TO SCHEDULE INSPECTIONS.



TRENCH/DRAINFIELD DATA

WIDTH	INLET	BOTTOM
3'	3'	6'
NUMBER OF TRENCHES		2
TOTAL LENGTH		105'
ABSORPTION AREA		315' + SIDEWALL
DISTRIBUTION BOX LEVEL		YES
DISTRIBUTION BOX BAFFLE		YES
DISTRIBUTION BOX PORT		YES

SEPTIC TANK DATA

SEPTIC TANK 1 LEVEL YES

MANUFACTURER BABYLON

CAPACITY 2000 GAL

SEAM LOC TOP

TANK LID DEPTH 1.5 - 3.5'

BAFFLES YES

BAFFLE FILTER NO

MANHOLE LOC FRONT + REAR

6" PORT LOC NONE

WATERTIGHT TEST NO

SLOTTED YES

DATE ON LID 6-22-18

PUMP/SEPTIC TANK LEVEL

MANUFACTURER _____

CAPACITY _____ GAL

SEAM LOC _____

TANK LID DEPTH _____

BAFFLES _____

BAFFLE FILTER _____

MANHOLE LOC _____

6" PORT LOC _____

WATERTIGHT TEST _____

SLOTTED _____

DATE ON LID _____

PRE-CONSTRUCTION:

7/1/18 Met S. Carroll and superintendent on site for layout. Tank and SDA cameras staked. Retaining wall also staked - location moved uphill from what was shown on plan b/c walkout location now at house corner (originally under deck). Tank in swale - at end of retaining wall where water will flow. Looked into options of moving w/ superintendent. Will make fall to tank w/ 3' or less cover + to trench inlet. (SC)

7/26/18 Met S. Carroll on site for layout. New tank location + retaining wall staked. Shot installation: contour + laid out 2x52' trenches. Shot elevations and tank will have 3' cover @ inlet. (SC)

7/30/18 On site while tank was set. No obvious cracks on bottom or sides. (SC)

7/31/18 T1 complete + left open @ ends for inspection - 3' wide, 2.5' to stone. S. Carroll adding stone to end of T2. D-box installed + connected to tank + trenches. Levelled speed levelers in D-box. Need house connection after retaining wall is installed. (SC)

8/9/18 Sewer line run from house to tank. Need house connection. (SC) 8/13/18 House connection made. (SC)

FINAL INSPECTOR Sarah Collins DATE OF APPROVAL 8/13/18