

1. ANY CHANGE TO THE LOCATIONS OR DEPTHS TO ANY COMPONENTS MUST BE APPROVED BY THE ENGINEER AND THE HOWARD COUNTY HEALTH DEPARTMENT PRIOR TO INSTALLATION. A

REVISED SITE PLAN MAY BE REQUIRED. 2. THE MAXIMUM EARTH COVER OVER THE TANK IS 3 FEET. GREATER EARTH COVER WILL REQUIRE

A HEAVY LOAD BEARING TANK.

3. ELECTRICAL WORK FOR THE INSTALLATION MUST BE PERFORMED BY A LICENSED ELECTRICIAN.

4. THE WELL, HO-17-0316, HAS BEEN FIELD LOCATED AND IS ACCURATELY SHOWN. 5. ALL WELLS AND SEPTIC SYSTEMS LOCATED WITHIN 100' OF THE PROPERTY BOUNDARIES AND 200' DOWN GRADIENT OF ANY WELLS AND/OR SEPTIC SYSTEMS HAVE BEEN SHOWN.

TRENCH DESIGN											
TRENCH	GROUND		1 41 11.11.00.01	DEPTH TO STONE FROM GROUND	DEPTH OF		EFFECTIVE DEPTH STARTS AT	EFFECTIVE DEPTH (D)	TRENCH DEPTH	WIDTH OF TRENCHES (W)	TRENCH 5PACING
		STONE ELEV.	574.2	3.5 FT	4.5 FT	570.2	7.5 FT	0.5 FT	8 FT	3 FT	10 FT
1A	578.2	574.7				570.2	7.5 FT	0.5 FT	8 FT	3 FT	10 FT
18	578.2	574.7	574.2	3.5 FT	4.5 FT	370.2					10 FT
01	577.2	573.7	573.2	3.5 FT	4.5 FT	569.2	7.5 FT	0.5 FT	Ø FT	3 FT	
2A	211.2	270.7				569.2	7.5 FT	0.5 FT	Ø FT	3 FT	10 FT
2A 2B	577.2	573.7	573.2	3.5 FT	4.5 FT	307.2	7.211				

LOW PRESSURE DOSING SYSTEM - INITIAL INSTALLATION												
TRENCH		PIPE INVERT	TRENCH	LATERAL PIPE	PERFORATION	HEAD	PERFORATION FLOW RATE (GPM)	PERFORATION SPACING (FT)	NUMBER OF ORIFICES	TRENCH FLOV RATE (GPM)		
	ELEV.	ELEV.	LENGTH (FT)	42.30	5/16	2	1.63	9.40	5	8.2		
1A	578.2	574.2	4/			2	1.63	9.40	5	8.2		
18	578.2	574.2	47	42.30	5/16	2			,			
	577.2	573.2	47	41.13	5/16	3	1.99	11.75	4	8.0		
2A	5//.2				5/16	3	1.99	11.75	4	8.0		
2B	577.2	573.2	47	41.13	3/10	-			I FLOW CATE	32.2		
	11/15/							TOTAL TRENCH	H FLOW KAIL	J4.4		

FRICTION LOSS IN 2" PIPE FITTINGS:

4 1/8 HB/VB x 4 FEET PER FITTING = 16 EQUIVALENT FEET OF PIPE 2 TEE/CROSS X 10 FEET PER FITTING = 20 EQUIVALENT FEET OF PIPE

UNION X 2 FEET PER FITTING = 2 EQUIVALENT FEET OF PIPE 1 ELBOWS × 7 FEET PER FITTING = 7 EQUIVALENT FEET OF PIPE TOTAL EQUIVALENT FEET OF PIPE = 45 FT

TOTAL LINEAR FEET OF 2" SCH. 40 PVC = 40 LF + 45 LF = 85 LF

DYNAMIC HEAD

85 LF X 2.22 FT PER 100 LF OF PIPE = 1.89 FT OF FRICTION HEAD DISTAL HEAD = 2.00 FT VERTICAL FROM PUMP OFF TO DISCHARGE = 4.63 FT OF STATIC HEAD TOTAL DYNAMIC HEAD = 8.52 FT

PIPE VOLUMES

40 LF (2" 5CH. 40 PIPE) X 17.4 GALLONS PER 100 LF = 6.96 GALLONS

166.9 LF (1.5" 5CH. 40 PIPE) X 10.6 GALLONS PER 100 LF = 17.7 GALLONS

MINIMUM DOSE = (5 X LATERAL PIPE VOLUME) + (FORCE MAIN & MANIFOLD) $= (5 \times 17.7) + (7.0)$

95.5 GALLONS IS MORE THAN 1/6 DESIGN FLOW (450/6=75) USE 134 GALLON DOSE (95.5 GALLON MINIMUM) (RUN TIME = 4 MIN (32.2 GPM X 4 = 128.8 GALLON DOSE)

= 95.5 GALLONS

PUMP NEEDS TO HANDLE 32.2 GPM AT 8.52 FT OF HEAD USE 0.3 HP (ZOELLER MODEL 50 SERIES PUMP)

BAT NOTES

SPECIFICATION IS 3 FEET.

- ANY CHANGE TO THE LOCATIONS OR DEPTHS TO ANY COMPONENTS MUST BE APPROVED BY THE ENGINEER AND THE HOWARD COUNTY HEALTH DEPARTMENT PRIOR TO INSTALLATION. A REVISED SITE PLAN MAY BE REQUIRED. 2. THE MAXIMUM COVER OVER THE BAT PER THE MANUFACTURER'S
- 3. THE BAT SYSTEM SHALL BE MAINTAINED AND OPERATED FOR THE LIFE OF THE SYSTEM.
- THE BAT SHALL BE OPERATED BY AND MAINTAINED BY A CERTIFIED SERVICE PROVIDER.
- WITHIN ONE MONTH OF INSTALLATION, A PERSON INSTALLING THE BAT SYSTEM SHALL REPORT TO THE MARYLAND DEPARTMENT OF THE ENVIRONMENT (MDE) IN A MANNER ACCEPTABLE TO MDE, THE ADDRESS AND DATE OF COMPLETION
- OF THE BAT INSTALLATION AND THE TYPE OF BAT INSTALLED. 6. ELECTRICAL WORK FOR THE BAT INSTALLATION MUST BE PERFORMED BY A LICENSED ELECTRICIAN.
- AN AGREEMENT AND EASEMENT MUST BE COMPLETED AND SIGNED BY ALL APPLICABLE PARTIES, AND RECORDED IN THE LAND RECORDS OF HOWARD COUNTY. 8. THE HEALTH DEPARTMENT REQUIRES DOCUMENTATION FOR THE START-UP CERTIFICATION FROM THE MANUFACTURER PRIOR TO
- FINAL APPROVAL OF THE INSTALLATION. 9. SURFACE RUNOFF SHALL BE DIRECTED AROUND THE BAT TANK.

INITIAL SYSTEM SEWAGE DISPOSAL SYSTEM DATA, DESIGN FOR 3 BEDROOMS LOADING RATE = 3 BEDROOMS X 150 GPD/BEDROOM = 450 GPD APPLICATION RATE = 0.8 EFFECTIVE SIDEWALL BEGINS AT 7.5 FEET TRENCH DEPTH = 8 FEET TRENCH WIDTH (W) = 3 FEET EFFECTIVE DEPTH (D) = 0.5 FEET SF OF DRAINFIELD = 450 GPD / 0.8 = 562.5 SF COEFFICIENT OF REDUCTION OF TRENCH LENGTH = (W+2)/(W+1+2D)=(3+2)/(3+1+(2x0.5))=1.0TRENCH LENGTH = 562.5 SF x 1.0 / 3 = 107.50 FEET (USE 4 TRENCHES AT 46.87 L.F.) TRENCH SPACING = 2D+W = ((2*0.5) + 3) = 4' USE 10'


15T REPLACEMENT SYSTEM SEWAGE DISPOSAL SYSTEM DATA, DESIGN FOR 3 BEDROOMS LOADING RATE = 3 BEDROOMS X 150 GPD/BEDROOM = 450 GPD APPLICATION RATE = 0.8 EFFECTIVE SIDEWALL BEGINS AT 7.5 FEET TRENCH DEPTH = 8 FEET TRENCH WIDTH (W) = 3 FEET EFFECTIVE DEPTH (D) = 0.5 FEET SF OF DRAINFIELD = 450 GPD / 0.8 = 562.5 SF COEFFICIENT OF REDUCTION OF TRENCH LENGTH =

(W+2)/(W+1+2D)=(3+2)/(3+1+(2x0.5))=1.0TRENCH LENGTH = 562.5 SF x 1.0 / 3 = 107.50 FEET (USE 4 TRENCHES AT 46.87 L.F.)


TRENCH SPACING = 20+W = ((2*0.5) + 3) = 4' USE 10'

2ND REPLACEMENT SYSTEM

SEWAGE DISPOSAL SYSTEM DATA, DESIGN FOR 3 BEDROOMS LOADING RATE = 3 BEDROOMS X 150 GPD/BEDROOM = 450 GPD APPLICATION RATE = 0.8 EFFECTIVE SIDEWALL BEGINS AT 7.5 FEET TRENCH DEPTH = 8 FEET TRENCH WIDTH (W) = 3 FEET EFFECTIVE DEPTH (D) = 0.5 FEET SF OF DRAINFIELD = 450 GPD / 0.8 = 562.5 SF COEFFICIENT OF REDUCTION OF TRENCH LENGTH = (W+2)/(W+1+2D)=(3+2)/(3+1+(2x0.5))=1.0TRENCH LENGTH = 562.5 SF x 1.0 / 3 = 187.50 FEET (USE 4 TRENCHES AT 46.87 L.F.) TRENCH SPACING = 2D+W = ((2*0.5) + 3) = 4' USE 10'



VICINITY MAP SCALE : 1" = 1200"



PROFILE HORIZONTAL SCALE: 1" = 30' VERTICAL SCALE: 1" = 3'

TRENCH DATA:

TRENCH 1A & 1B:

TRENCH 2A & 2B:

INV. IN = 573.2

INV. IN = 574.2

EX. GROUND ABOVE = 578.2

EX. GROUND ABOVE = 577.2

BOTTOM TRENCH = 570.2

BOTTOM TRENCH = 569.2

Howard County Health Department Hank Oswald 1/28/2021

FFE 581.3 BSE 571.3 INV. OUT OF HOUSE = 576.71 PROP. GROUND AT CLEANOUT #1 = 578.5 INV. INTO CLEANOUT = 576.61 INV. OUT OF CLEANOUT = 576.51 PROP. GROUND AT CLEANOUT #2 = 577.8 INV. INTO CLEANOUT = 576.11 INV. OUT OF CLEANOUT = 576.01 EX. GROUND AT BAT TANK = 579.5 PROP. GRADE ABOVE BAT TANK = 579.0 TOP OF BAT TANK = 578.00 INV. INTO BAT TANK = 575.49 INV. OUT OF BAT TANK = 575.16 EX. GROUND AT PUMP TANK = 579.5 PROP GRADE ABOVE PUMP TANK = 579.0

TOP OF PUMP TANK = 576.14 INV. INTO PUMP TANK = 575.06 INV. OUT OF PUMP TANK = 577.19


> SITE PLAN FOR BAT INSTALLATION RIZK PROPERTY

ZONING: RC-DEO

TAX MAP No. 9 GRID No. 8 PARCEL No. 75

THIRD ELECTION DISTRICT HOWARD COUNTY, MARYLAND SCALE: 1"=50' DATE: JANUARY 2021

LOT 2



3.25 AC.

FOREST CONSERVA


EASEMENT 1 (RETEN


5T#20-PUBLIC ROW (NOT FEE-SIMPLE) - PRIVATE MAINTENANCE PROPOSED FENCE (6%3

OWNER


CHARBEL RIZK 1445 UNDERWOOD ROAD SYKESVILLE, MARYLAND 21784

FISHER, COLLINS & CARTER, INC. ELLICOTT CITY, MARYLAND 21042






NOT TO SCALE




NOTE: THIS DETAIL IS TO BE USED FOR FLOAT CONFIGURATION ONLY - SEE DETAIL ABOVE FOR TANK DIMENSIONS AND ACTUAL LOCATION OF ACCESS COVER.

PUMP ALARMS / INFORMATION A PUMP OFF: 572.56 PUMP ON : 572.90 HIGH WATER ALARM : 573.24 TOP OF ACCESS COVER : 579.00 TOP OF TANK : 576.14 BOTTOM OF TANK : 570.56 G DISCHARGE OUT OF TANK : 577.19 H INVERT INTO TANK : 575.06


NOTE: SEPTIC SYSTEM ALARM WILL BE ON A CIRCUIT SEPARATE FROM ANY OTHER SEPTIC SYSTEM COMPONENTS OR ALARMS.



USE 0.3 HP (ZOELLER MODEL 50 SERIES PUMP)





INITIAL TRENCH DETAIL



PERFORATED PVC LATERAL PIPE BLOWUP DETAIL

NOTE: SEPTIC SYSTEM ALARM WILL BE ON A CIRCUIT SEPARATE FROM ANY OTHER SEPTIC SYSTEM COMPONENTS OR ALARMS.









FIGURE 4.1 CENTER FEED MANIFOLD DISTRIBUTION NETWORK

FISHER, COLLINS & CARTER, INC.

CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS

ELLICOTT CITY, MARYLAND 21042

OWNER CHARBEL RIZK 1445 UNDERWOOD ROAD SYKESVILLE, MARYLAND 21784



1/10/21 "Professional certification. I hereby certify that these documents were prepared by me, and that I am a duly Licensed Professional Engineer under the laws of the State of Maryland, License No. 30306, Expiration Date 1-12-22."

SITE PLAN FOR BAT INSTALLATION RIZK PROPERTY

LOT 2

ZONING: RC-DEO TAX MAP No. 9 GRID No. 8 PARCEL No. 75 THIRD ELECTION DISTRICT HOWARD COUNTY, MARYLAND SCALE: 1"=60' DATE: JANUARY 2021