

Page, Shepsura

From: Page, Shepsura
Sent: Friday, August 29, 2025 8:59 AM
To: Jet Septic
Cc: Rappaport, Ryan; Wolf, Kevin; Burns, Matthew
Subject: 13499 Triadelphia Rd- Septic Design Plan Needed
Attachments: 13499 Triadelphia Rd- Map w contours.pdf

Good Morning,

Please see attached map of 13499 Triadelphia Rd, feel free to use for your plan submitted. The specs for the septic system repair to be included are: 2 x 68' Trenches, 2' wide, 4' inlet, 9' bottom, side wall credit 5'-9'.

Please also indicate the following:

- Well Location with tag #HO-04-7658 (label well on plan) & well arc
- Label House
- Existing Tank Loc indicating size
- Existing Drywell to be abandoned
- Trench location with length of trenches & 9' minimum between trenches
- Trenches drawn as trenches & septic lines as single lines
- Distance from closest property line (we measured 14' from the bottom trench to the hedges)
- Distance to property lines (septic tank & trench ends)
- Full name & contact of the homeowner
- Full name of who the plan is prepared by w/ company contact info
- Title (13499 Triadelphia Rd- Septic Design Plan)

Thanks,

Shepsura Page, EH Specialist
Well & Septic Program
Howard County Health Department
8930 Stanford Blvd.
Columbia, MD 21045
410-313-1789 (Office)
410-313-2648 (Fax)
www.hchealth.org
spage@howardcountymd.gov



twitter.com/HoCoHealth



facebook.com/HoCoHealth



instagram.com/hocohealth

CONFIDENTIALITY NOTICE